



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 16, 2020

SUBJECT: FAU Route 1488 (47th Street)
Project STP-PGTQ(239)
Section 2020-148-RS-SW&PP
Cook County
Contract No. 62M20
Item No. 93, July 31, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions.
2. Added pages 127-129 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

MOBILIZATION (BDE) 97
PORTLAND CEMENT CONCRETE (BDE) 98
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE) 99
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) 100
STEEL PLATE BEAM GUARDRAIL MANUFACTURING (BDE) 111
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) 112
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 112
TEMPORARY PAVEMENT MARKING (BDE) 113
TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (BDE) 116
TRAFFIC CONTROL DEVICES - CONES (BDE) 117
TRAINING SPECIAL PROVISIONS (BDE) 117
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION 120
WARM MIX ASPHALT (BDE) 122
WEEKLY DBE TRUCKING REPORTS (BDE) 124
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 124
WORKING DAYS (BDE) 126
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC) 127

Revised 7/16/2020

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Intersection of 47th Street and Veeck Park Entrance, Hinsdale, Cook County

- All excavation planned at the northwest quadrant, and northeast quadrant at the intersection of 47th Street and Veeck Park Entrance. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Shoulder Construction Excavation, 47th Street, Hinsdale, Cook County

- Station 28+25 to Station 35+00 (CL 47th Street), 0 to 35 feet LT. All excavation planned for shoulder construction excavation. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of 47th Street and Commonwealth Avenue, Western Springs, Cook County

- All excavation planned at the southwest quadrant, and southeast quadrant at the intersection of 47th Street and Commonwealth Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Shoulder Construction Excavation, 47th Street, Western Springs, Cook County

- Station 45+75 to Station 49+60 (CL 47th Street), 0 to 35 feet LT. All excavation planned for shoulder construction excavation. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of 47th Street and Fair Elms Avenue, Western Springs, Cook County

- All excavation planned at the southwest quadrant, and southeast quadrant at the intersection of 47th Street and Fair Elms Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Added 7/16/2020

Intersection of 47th Street and Central Avenue (west intersection), Western Springs, Cook County

- All excavation planned at the southwest quadrant, and southeast quadrant at the intersection of 47th Street and Central Avenue (west intersection). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of 47th Street and Central Avenue (east intersection), Western Springs, Cook County

- All excavation planned at the northwest quadrant, northeast quadrant, and southwest quadrant at the intersection of 47th Street and Central Avenue (east intersection). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of 47th Street and Woodland Avenue (west intersection), Western Springs, Cook County

- All excavation planned at the southwest quadrant, and southeast quadrant at the intersection of 47th Street and Woodland Avenue (west intersection). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of 47th Street and Woodland Avenue (east intersection), Western Springs, Cook County

- All excavation planned at the northwest quadrant, and northeast quadrant at the intersection of 47th Street and Woodland Avenue (east intersection). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of 47th Street and Grand Avenue, Western Springs, Cook County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of 47th Street and Grand Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Added 7/16/2020

Intersection of 47th Street and Lawn Avenue (west intersection), Western Springs, Cook County

- All excavation planned at the northwest quadrant, and northeast quadrant at the intersection of 47th Street and Lawn Avenue (west intersection). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of 47th Street and Lawn Avenue (east intersection), Western Springs, Cook County

- All excavation planned at the southwest quadrant, and southeast quadrant at the intersection of 47th Street and Lawn Avenue (east intersection). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of 47th Street and Wolf Road, Western Springs, Cook County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of 47th Street and Wolf Road. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:

None

Additional information on the above sites collected during the regulated substances due-diligence process is available through the District's Environmental Studies Unit (DESU).

Added 7/16/2020