



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 20, 2026

SUBJECT FAP Route 344A (127th St)
Project NHPP-PW88(405)
Section FAP 0344A 23 C&J
Cook County
Contract No. 62V45

Item No. 004, July 31st, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised pages i-ii of the Table of Contents of the Special Provisions.
3. Revised pages 1-2 of the Special Provisions.
4. Revised sheet 4 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS (D1)	1
PUBLIC CONVENIENCE AND SAFETY (D1)	2
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	2
TRAFFIC CONTROL PLAN (D1)	3
STATUS OF UTILITIES (D-1)	4
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1)	6
ADJUSTMENTS AND RECONSTRUCTIONS (D1).....	14
CURB OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (D1)	15
ENGINEER'S FIELD OFFICE TYPE A (D1)	16
TEMPORARY INFORMATION SIGNING	17
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)	18
TRAFFIC CONTROL AT AT-GRADE RR CROSSINGS	19
FRICTION AGGREGATE (D1).....	19
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1)	22
DETECTOR LOOP	24
COILABLE NON-METALLIC CONDUIT	26
DETECTOR LOOP REPLACEMENT AND/OR INSTALLATION (ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS)	26
TRAFFIC CONTROL AND PROTECTION (ARTERIALS) (D1).....	29
CLEANING EXISTING DRAINAGE STRUCTURES (D1)	30
MINERALIZED CARBON DIOXIDE CONCRETE (D-1)	30
TEMPORARY TRAFFIC SIGNAL TIMING.....	32
PARTIAL DEPTH PATCHING (SPECIAL).....	33
RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE)	34
CSXT PERMITTING	35
CSXT INSURANCE REQUIREMENTS	49
CSXT RIGHT OF ENTRY APPLICATION	51
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....	55
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE)	56
COMPENSABLE DELAY COSTS (BDE).....	73
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	77
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE)	79

PAVEMENT MARKING (BDE)	80
PAVEMENT PATCHING (BDE)	80
PERFORMANCE GRADED ASPHALT BINDER (BDE)	81
PREFORMED PLASTIC PAVEMENT MARKING (BDE)	86
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)	87
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	88
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	89
SIGN PANELS AND APPURTENANCES (BDE)	93
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	94
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	95
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	96
SUBMISSION OF BIDDERS LIST INFORMATION (BDE).....	96
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE).....	97
SURVEYING SERVICES (BDE)	98
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	99
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	99
WORK ZONE WIDTH RESTRICTION (BDE).....	101
WORKING DAYS (BDE)	101
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE).....	102
WEEKLY DBE TRUCKING REPORTS (BDE).....	105

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1 2022, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of FAP Route 344A (127th St), Project NHPP-PW88(405), Section FAP 0344A 23 C&J, Cook County, Contract No. 62V45 and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

FAP Route 344A (127th St)
Project NHPP-PW88(405)
Section FAP 0344A 23 C&J
Cook County
Contract No. 62V45

LOCATION OF PROJECT

This project begins on 127th St East of Cal sag channel. It continues in an eastern direction until Artesian Ave for a gross and net length of 17434.0 feet (3.3 miles). This project is located within the City of Alsip and Blue Island in Cook County.

DESCRIPTION OF PROJECT

The improvement consists of HMA pavement resurfacing with binder and surface courses, class B patching, cleaning and sealing of longitudinal pavement joints between traffic lanes and curb and gutter, placement of thermoplastic and modified urethane pavement markings, and all incidental and collateral work necessary to complete the improvements at the locations shown on the plans and described herein.

MAINTENANCE OF ROADWAYS (D1)

Effective: September 30, 1985 Revised: November 1, 1996

Beginning on the date that work begins on this project, the Contractor shall assume responsibility for normal maintenance of all existing roadways within the limits of the improvement. This normal maintenance shall include all repair work deemed necessary by the Engineer, but shall not include snow removal operations. Traffic control and protection for maintenance of roadways will be provided by the Contractor as required by the Engineer.

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the Standard Specifications.

PUBLIC CONVENIENCE AND SAFETY (D1)

Effective: May 1, 2012

Revised: July 15, 2012

Add the following to the end of the fourth paragraph of Article 107.09:

"If the holiday is on a Saturday or Sunday, and is legally observed on a Friday or Monday, the length of Holiday Period for Monday or Friday shall apply."

Add the following sentence after the Holiday Period table in the fourth paragraph of Article 107.09:

"The Length of Holiday Period for Thanksgiving shall be from 5:00 AM the Wednesday prior to 11:59 PM the Sunday After"

Delete the fifth paragraph of Article 107.09 of the Standard Specifications:

"On weekends, excluding holidays, roadways with Average Daily Traffic of 25,000 or greater, all lanes shall be open to traffic from 3:00 P.M. Friday to midnight Sunday except where structure construction or major rehabilitation makes it impractical."

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either "uncontaminated soil", hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Intersection of IL 83 (127th Street) and S Laramie Avenue, Alsip, Cook County

- Station 14+00 to Station 27+00 (CL IL 83), 0 to 40 LT and 0 to 40 RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals

Work Zones. Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: **None**

Revised 7-20-2026