

SUMMARY OF QUANTITIES

IDOT CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITIES	CMM		F 80% FED./20% STATE		CMM 80% FED./20% STATE		
				J000-2A		X271-2A	Y007	Y031-IF	Y030-IE	J000-2A
				ROADWAY 80% FED./20% STATE	ROADWAY 60% STATE 40% GURNEE	BRIDGE	RETAINING WALLS	TRAFFIC SIGNALS	LIGHTING	SIGNING
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	474			474				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	377	377						
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	611	611						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	9497	9497						
42400610	TEMPORARY SIDEWALK	SQ FT	3334	3334						
42400800	DETECTABLE WARNINGS	SQ FT	215	215						
44000100	PAVEMENT REMOVAL	SQ YD	31722	31722						
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	8131	8131						
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1186	1186						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6800	6800						
44000600	SIDEWALK REMOVAL	SQ FT	10978	10978						
44004250	PAVED SHOULDER REMOVAL	SQ YD	7314	7314						
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	22	22						
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	73	73						
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2429	2429						
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	4976	4976						
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	568	568						
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	17549	17549						
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1				
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1				
50102400	CONCRETE REMOVAL	CU YD	7				7			
50157300	PROTECTIVE SHIELD	SQ YD	466			466				
50200100	STRUCTURE EXCAVATION	CU YD	16681	8		12595	4078			
50300225	CONCRETE STRUCTURES	CU YD	2537			1458	1079			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3094			2025	1069			
50300260	BRIDGE DECK GROOVING	SQ YD	6488			6488				
50300300	PROTECTIVE COAT	SQ YD	10856			8460	2396			
50500305	ERECTING STRUCTURAL STEEL	L SUM	1			1				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	20440				20440			
50500505	STUD SHEAR CONNECTORS	EACH	13156			10230	2926			
50700209	UNTREATED TIMBER LAGGING	SQ FT	13906				13906			
50800105	REINFORCEMENT BARS	POUND	323320	2650			320670			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	970520			719980	250540			
50800515	BAR SPLICERS	EACH	6188			6188				
51202210	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	168				168			
51202230	FURNISHING SOLDIER PILES (W SECTION)	FOOT	8051				8051			
51202305	DRIVING PILES	FOOT	14959			14959				
51203200	TEST PILE METAL SHELLS	EACH	4			4				
51500100	NAME PLATES	EACH	1			1				
51603000	DRILLED SHAFT IN SOIL	CU YD	1387				1387			

PLAN
NO. _____
DATE _____
BY _____
SUBMITTED _____
CHECKED _____
ALIGNED _____
CADD FILE NAME _____

PROFILE
NO. _____
DATE _____
BY _____
SUBMITTED _____
CHECKED _____
STRUCTURE NOTATIONS CHECKED _____

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
U.S. 41 (SKOKIE HIGHWAY)
AT IL ROUTE 132

SUMMARY OF QUANTITIES
SHEET 2 OF 9

SCALE: NONE DRAWN BY: _____
DATE: MAY 12, 2008 CHECKED BY: _____