

### SUMMARY OF QUANTITIES

IDOT CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITIES	CMM		F 80% FED./20% STATE		CMM 80% FED./20% STATE		
				J000-2A		X271-2A	Y007	Y031-1F	Y030-1E	J000-2A
				ROADWAY 80% FED./20% STATE	ROADWAY 60% STATE 40% GURNEE	BRIDGE	RETAINING WALLS	TRAFFIC SIGNALS	LIGHTING	SIGNING
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1						
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1						
Z0018800	DRAINAGE SYSTEM	L SUM	1			1				
* Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	6	6						
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	12	12						
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	9	9						
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1						
Z0067500	STEEL CASINGS 16"	FOOT	60			60				
Z0067700	STEEL CASINGS 20"	FOOT	20			20				
o Z0076600	TRAINEES	HOUR	7500	7500						
51200960	FURNISHING METAL SHELL PILES 14" x 0.375"	FOOT	14959			14959				
* X0326148	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	16						16	
* X0326149	UNIT DUCT, WITHOUT CABLE, IN TRENCH 2"	FOOT	8100						8100	
X0326150	ERECTING MODULAR EXPANSION JOINT 6"	FOOT	99			99				
X3120050	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	48941	48941						
X6370015	CONCRETE BARRIER, SPECIAL, 32" HEIGHT	FOOT	649	649						
X0326151	CONCRETE ACCENT PAVER, REMOVE AND STORE	SQ FT	156	156						
X0326152	CONCRETE ACCENT PAVER RE-INSTALLATION	SQ FT	156	156						
X0326153	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 42, RISE 27	FOOT	164	164						
X0326154	STORM SEWER (WATER MAIN REQUIREMENTS) 72 INCH	FOOT	599			599				
X0326155	STORM SEWER (WATER MAIN REQUIREMENTS) 78 INCH	FOOT	543			543				
* X8770430	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 28 FT. & 24 FT.	EACH	1					1		
* X8808118	OPTICALLY PROGRAMMED SIGNAL HEAD, L E D, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1					1		
* X8808120	OPTICALLY PROGRAMMED SIGNAL HEAD, L E D, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	5					5		
X0326156	SANITARY SEWER, PVC (D3034) SDR 26, 12"	FOOT	20			20				
X0326157	TEMPORARY ELECTRIC SERVICE DISCONNECTION	EACH	1						1	
X0326158	ERECTING HIGH LOAD MULTI-ROTATION BEARINGS, GUIDED EXPANSION 250K	EACH	20			20				
X0326159	ERECTING HIGH LOAD MULTI-ROTATION BEARINGS, GUIDED EXPANSION, 850K	EACH	10			10				
X0326160	POROUS GRANULAR EMBANKMENT, SUBGRADE (SPECIAL)	CU YD	829	829						

o 1080  
\* specialty items

• 100% Village of Gurnee - 1006

DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 SURVEYED: \_\_\_\_\_  
 ALIGNED: \_\_\_\_\_  
 CHECKED: \_\_\_\_\_  
 P.L. OF WAY CHECKED: \_\_\_\_\_  
 NOTE BOOK NO. \_\_\_\_\_  
 CAD FILE NAME: \_\_\_\_\_

DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 SURVEYED: \_\_\_\_\_  
 PLOTTED: \_\_\_\_\_  
 CHECKED: \_\_\_\_\_  
 B.M. NOTED: \_\_\_\_\_  
 STRUCTURE NOTATIONS: CHFD  
 NOTE BOOK NO. \_\_\_\_\_  
 CAD FILE NAME: \_\_\_\_\_

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 U.S. 41 (SKOKIE HIGHWAY)  
 AT IL ROUTE 132  
 SUMMARY OF QUANTITIES  
 SHEET 9 OF 9  
 SCALE: NONE  
 DATE: MAY 12, 2008  
 DRAWN BY:  
 CHECKED BY:

Rev.