

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|--|--------|------------------------|----------------------------|--|--|--|
| CODE NO | ITEM | UNIT | URBAN TOTAL QUANTITIES | 80% FED. 20% STATE I000-2A | | | |
| 20201006 | GRADING AND SHAPING SHOULDERS | UNIT | 190 | 190 | | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 14 | 14 | | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 67 | 67 | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 10 | 10 | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SO YD | 248 | 248 | | | |
| 40600990 | TEMPORARY RAMP | SO YD | 248 | 248 | | | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 232 | 232 | | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 2781 | 2781 | | | |
| 42001300 | PROTECTIVE COAT | SO YD | 35 | 35 | | | |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SO YD | 33100 | 33100 | | | |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 112 | 112 | | | |
| 44002221 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5/4" | SO YD | 788 | 788 | | | |
| 44201753 | CLASS D PATCHES, TYPE II, 9 INCH | SO YD | 361 | 361 | | | |
| 44201757 | CLASS D PATCHES, TYPE III, 9 INCH | SO YD | 35 | 35 | | | |
| 44201759 | CLASS D PATCHES, TYPE IV, 9 INCH | SO YD | 350 | 350 | | | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 758 | 758 | | | |
| 55039700 | STORM SEWERS TO BE CLEANED | FOOT | 1050 | 1050 | | | |
| 60300105 | FRAMES AND GRATES TO BE ADJUSTED | EACH | 4 | 4 | | | |
| *63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 850 | 850 | | | |
| *63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 4 | 4 | | | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 850 | 850 | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 3 | 3 | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | 1 | | | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | | | |

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|---|-------|------------------------|----------------------------|--|--|--|
| CODE NO | ITEM | UNIT | URBAN TOTAL QUANTITIES | 80% FED. 20% STATE I000-2A | | | |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 | | | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 6444 | 6444 | | | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SO FT | 37 | 37 | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 14493 | 14493 | | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 102 | 102 | | | |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 582 | 582 | | | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 155 | 155 | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SO FT | 5990 | 5990 | | | |
| *78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SO FT | 37 | 37 | | | |
| *78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 14493 | 14493 | | | |
| *78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 102 | 102 | | | |
| *78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 582 | 582 | | | |
| *78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 155 | 155 | | | |
| *78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 490 | 490 | | | |
| *78200405 | GUARDRAIL MARKERS | EACH | 12 | 12 | | | |
| *78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 4 | 4 | | | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 416 | 416 | | | |
| *88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 202 | 202 | | | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SO FT | 51.4 | 51.4 | | | |
| X4067107 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50 | TON | 1304 | 1304 | | | |
| Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 4 | 4 | | | |

* SPECIALITY ITEMS
 NON-PARTICIPATING ITEMS 100% STATE

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.U. 2721 (KEAN AVE.)
111TH ST. TO US 12/20 (95TH ST.)

Rev. 7-24-08