

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, LIST OF STATE STANDARDS, SCOPE OF WORK AND GENERAL NOTES IL. RTE. 58 & IL. RTE. 72
3	SUMMARY OF QUANTITIES IL. RTE. 58 & IL. RTE. 72
4	TYPICAL SECTIONS AND DETAILS IL. RTE. 58 & IL. RTE. 72
5 - 6	ALIGNMENT, TIES AND PAVEMENT MARKINGS IL. RTE. 58 & IL. RTE. 72
7 - 8	PLAN AND PROFILE IL. RTE. 58 & IL. RTE. 72
9	CONSTRUCTION STAGING AND MAINTENANCE OF TRAFFIC NOTES IL. RTE. 58 & IL. RTE. 72
10 - 11	SUGGESTED TRAFFIC CONTROL AND STAGING STAGE I TO STAGE IV IL. RTE. 58 & IL. RTE. 72
12 - 23	STRUCTURAL DRAWINGS - IL. RTE. 58 OVER SALT CREEK
24 - 35	STRUCTURAL DRAWINGS - IL. RTE. 72 OVER SALT CREEK
36	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT (BD-24)
37	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)
38	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC-11)
39	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)

LIST OF STATE STANDARDS

STANDARD NO.	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
515001-02	NAME PLATE FOR BRIDGES
606001-03	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
606301-03	PC CONCRETE ISLANDS AND MEDIANS
630001-07	STEEL PLATE BEAM GUARDRAIL
631006-05	TRAFFIC BARRIER TERMINAL, TYPE 1B
631031-04	TRAFFIC BARRIER TERMINAL, TYPE 6
631046-03	TRAFFIC BARRIER TERMINAL, TYPE 10
635006-02	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-01	REFLECTOR MARKER AND MOUNTING DETAILS
701601-05	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701606-05	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701901	TRAFFIC CONTROL DEVICES
704001-04	TEMPORARY CONCRETE BARRIER

SCOPE OF WORK

THE SCOPE OF WORK FOR THIS PROJECT CONSIST OF:

- REMOVE AND REPLACE MEDIAN AS NEEDED FOR CONSTRUCTION STAGING RUN-AROUND.
- SUPERSTRUCTURE REPLACEMENT INCLUDING THE REMOVAL AND THE REPLACEMENT OF THE PPC DECK BEAMS.
- CONSTRUCT NEW PARAPETS AND CONCRETE WEARING SURFACE.
- GUARDRAIL IMPROVEMENTS AT THE BRIDGE PARAPETS.

GENERAL NOTES

1. FORTY-EIGHT HOURS BEFORE STARTING EXCAVATION, THE CONTRACTOR WILL CALL J.U.L.I.E. AT 1-800-892-0123 OR 811 TO HAVE THE LOCATION OF EXISTING UTILITIES STAKED.
2. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
3. THE CONTRACTOR SHALL PROTECT EXISTING AND NEW UTILITIES AND SHALL BRACE AND SUPPORT THE UTILITIES PROPERLY IN ORDER TO PREVENT SETTLEMENT, DISPLACEMENT, OR DAMAGE TO THE UTILITIES. THE PROTECTION OF THE UTILITIES AS SPECIFIED HEREIN WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT.
4. LOCATIONS OF EXISTING UTILITIES SHOWN ON THE PLANS ARE FROM BEST AVAILABLE RECORD INFORMATION AND MUST BE FIELD VERIFIED BY THE CONTRACTOR.
5. SAW CUTTING PRIOR TO THE REMOVAL OF ANY ITEMS NOTED ON THE PLANS OR AS DIRECTED BY THE ENGINEER SHALL BE INCLUDED IN THE COST OF THE ITEMS BEING REMOVED.
6. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
7. THE CONTRACTOR SHALL USE CARE IN REMOVING OR EXCAVATING NEAR ALL EXISTING ITEMS WHICH WILL REMAIN. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
8. POLLUTION CONTROL: THE CONTRACTOR SHALL BE REQUIRED TO COMPLY WITH STATE REGULATIONS REGARDING AIR, WATER AND NOISE POLLUTION.
9. WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AS WELL AS ADJOINING RESIDENTIAL AREAS.
10. 10-FOOT TRANSITIONS SHALL BE USED TO MATCH PROPOSED ITEMS OF WORK TO EXISTING ITEMS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEM OF WORK SPECIFIED.
11. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS, AS REQUIRED, PRIOR TO COMMENCING WITH CONSTRUCTION.
12. WHERE SECTION OR SUB-SECTION MARKERS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED AGENT OR LAND SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
13. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO ASSURE THAT NO DEBRIS FALLS IN THE CREEK. THE COST OF THIS WORK SHALL BE INCLUDED AS PART OF REMOVAL OF EXISTING STRUCTURE.
14. THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.
15. AT LEAST TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS, THE CONTRACTOR SHALL CONTACT THE AREA TRAFFIC FIELD ENGINEER, WALTER CZARNY (773) 685-8386.
16. THE CONTRACTOR SHALL BE RESTRICTED TO WORKING ON IL. RTE. 58 FIRST AND IL. RTE. 72 SECOND. NO LANE CLOSURES WILL BE ALLOWED ON IL. RTE. 72 UNTIL ALL LANES ON IL. RTE. 58 ARE OPEN TO TRAFFIC.
17. THE CONTRACTOR SHALL COORDINATE THE MAINTENANCE OF TRAFFIC ON IL. RTE. 58 WITH THE NEW WILKE ROAD IMPROVEMENT. THE SUGGESTED TRAFFIC CONTROL AND STAGING SHALL BE MODIFIED AS NEEDED TO ACCOMMODATE THE NEW WILKE ROAD IMPROVEMENT. THE COST OF THIS WORK SHALL BE INCLUDED IN THE CONTRACT PRICE FOR TRAFFIC CONTROL AND PROTECTION (SPECIAL).

NOTE: BOXED ITEMS ARE INCIDENTAL.

FILE NAME = 68055 index.dgn
PLOT DATE = 6/25/2008



DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - E.J.M.	REVISED -
DATE - APRIL 21, 2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, LIST OF STATE STANDARDS, SCOPE OF WORK
AND GENERAL NOTES IL. RTE. 58 & IL. RTE. 72**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
559/541	2008-007 B	COOK	39	2
CONTRACT NO. 60D55				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				