

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1300	1922 RS-4	COOK	25	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 60E46

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES 80% FED. 20% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	86	86				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	36	36				
40600300	AGGREGATE (PRIME COAT)	TON	90	90				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	23	23				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	437	437				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	900	900				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3755	3755				
42001300	PROTECTIVE COAT	SQ YD	80	80				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	150	150				
42400800	DETECTABLE WARNINGS	SQ FT	24	24				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	44700	44700				
44000600	SIDEWALK REMOVAL	SQ FT	150	150				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	218	218				
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	2674	2674				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1849	1849				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	144	144				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	200	200				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	532	532				
60254330	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1				
60254340	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	8	8				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES 80% FED. 20% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6600	6600				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	400	400				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	33700	33700				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1870	1870				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1250	1250				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	520	520				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2600	2600				
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	400	400				
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33700	33700				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1870	1870				
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1250	1250				
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	520	520				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	376	376				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	356	356				
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	1498	1498				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1761	1761				
NP 20018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	39	39				
20048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				

* SPECIALITY ITEMS
NP: Non-participating

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

5/20/2008 10:50:08 AM C:\p19508\19508.dwg