



NOTES:

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE FULL DEPTH PATCHES
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PAVEMENT PATCHING FOR
HMA SURFACED PAVEMENT**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1300	1922 RS-4	COOK	25	15
BD400-04 (BD-22)			CONTRACT NO. 60E46	
<small>FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT</small>				

FILE NAME =	USER NAME = w1greendp	DESIGNED - R. SHAH	REVISED - A. ABBAS 01-20-98
\\dist1\dfs2\users\w1greendp\Desktop\Central Rd. Details\bd22.dgn		DRAWN -	REVISED - A. ABBAS 04-27-98
PLOT SCALE = 50,000' / IN.		CHECKED -	REVISED - R. BORO 01-01-07
PLOT DATE = 5/20/2008		DATE - 10-25-94	REVISED - R. BORO 09-04-07

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.