

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	100% STATE URBAN	
				1000	1007
				ROADWAY	BX CULV
20200100	EARTH EXCAVATION	CU YD	42	42	
20300100	CHANNEL EXCAVATION	CU YD	28		28
20700220	POROUS GRANULAR EMBANKMENT	CU YD	65	65	
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	18	18	
25000310	SEEDING, CLASS 4	ACRE	.01	.01	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	.2	.2	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	.2	.2	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	.2	.2	
25100630	EROSION CONTROL BLANKET	SQ YD	18	18	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	.4	.4	
28000300	TEMPORARY DITCH CHECKS	EACH	2	2	
28000400	PERIMETER EROSION BARRIER	FOOT	28	28	
28100107	STONE RIPRAP, CLASS A4	SQ YD	26.6		26.6
28200200	FILTER FABRIC	SQ YD	95		95
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4	0.4	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	188	188	
50102400	CONCRETE REMOVAL	CU YD	11		11
50200100	STRUCTURE EXCAVATION	CU YD	23.2		23.2
50300225	CONCRETE STRUCTURES	CU YD	22.2		22.2
50300300	PROTECTIVE COAT	SQ YD	113		113
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1310		1310
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2070		2070
51500100	NAME PLATES	EACH	1		1
54011006	PRECAST CONCRETE BOX CULVERT 10'x6'	FOOT	32		32
* 63000005	STEEL PLATED BEAM GUARD RAIL, TYPE B	FOOT	576	576	
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	28	28	
* 63200307	STEEL PLATE BEAM GUARDRAIL REMOVAL, ATTACHED TO STRUCTURE	FOOT	28	28	
63200310	GUARDRAIL REMOVAL	FOOT	576	576	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	100	100	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	100	100	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	260	260	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6	
* 78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	4	4	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6	
* 78200500	BARRIER WALL MARKERS	EACH	10	10	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6	
X0321099	GEOTEXTILE RETAINING WALL	SQ YD	51		51
X0322256	TEMPORARY INFORMATIONAL SIGNING	SQ FT	50	50	
X0322641	TEMPORARY CLEAR WATER DIVERSION	L SUM	1		1
X0325350	CONCRETE DECK REMOVAL	SQ FT	520		520
X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	5	5	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	90	90	
XX007025	COARSE AGGREGATE BACKFILL (SPECIAL)	CU YD	208	208	
XZ137300	TEMPORARY SHORING	L SUM	1		1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	

* SPECIALTY ITEMS

LOWCO, INC.
CONSULTING ENGINEERS
1979 N. MILL ST., SUITE 210
NAPERVILLE, ILLINOIS 60563 PH: 630/517-9100

USER NAME = #USER#	DESIGNED - MJY	REVISED -
PLOT SCALE = #SCALE#	DRAWN - ZDA & ST	REVISED -
PLOT DATE = #DATE#	CHECKED - MJY	REVISED -
	DATE - 05/27/2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL ROUTE 31**

SCALE: NONE SHEET NO. 3 OF 17 SHEETS STA. 37+24 TO STA. 37+60

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-T-1	KANE	17	3
D-91-076-08		CONTRACT NO. 60E50		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		