F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-049 PP	COOK & DUPAGE	13	3

FED. ROAD DIST. NO. 1 | ILLINOIS | HIGHWAY PROJECT

CONTRACT NO. 60E98

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: COOK COUNTY 1000-2A	DUPAGE COUNTY 1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	0.5	0.5				
40600300	AGGREGATE (PRIME COAT)	TON	4	2	2				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	2	3				
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.5	0.5				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	236	115	121				
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	229	86	143				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	2033	766	1267				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	10	0	10				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	16	0	16				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	93	93	0				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1	2				
67100100	MOBILIZATION	L SUM	1	0.5	0.5				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3136	1288	1848				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.5				

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					

* SPECIALTY ITEMS

Rev. 7-22-08

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 6/27/2008

6/27/2008
c:\pwworking\dot\d1135508\design_sa.dgn

...\projects\d1135508\design_sa.dgn 6/27/2008 2:27:14 PM User=wilgreendp