

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
				1000-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4	4					
40600300	AGGREGATE (PRIME COAT)	TON	17	17					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	25	25					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	512	512					
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	422	422					⚠
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	515	515					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	8353	8353					⚠
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	44	44					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	146	146					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5836	5836					⚠
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	58	58					
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	80	80					
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	468	468					
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	300	300					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	50	50					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50	50					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						

\* SPECIALTY ITEMS

⚠ Rev. 7-22-08

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

PLOT DATE: 6/25/2008

LOCATIONS FOR INTERSTATE 55	REPAIR LENGTH (FT)	REPAIR WIDTH (FT)	REPAIR AREA (SF)	REPAIR AREA (SY)	SURFACE TYPE	REPAIR WORK
NB I-55 @ LAGRANGE RD - SOUTH EXIT RAMP	9	15	135	15	HMA	HMA SURF REM & RESURF
	5	12	60	7	HMA	HMA SURF REM & RESURF
	12	12	144	16	HMA	HMA SURF REM & RESURF
	12	12	144	16	HMA	HMA SURF REM & RESURF
NB I-55 @ LAGRANGE RD - NB ENTRANCE RAMP	10	14	140	16	HMA	HMA SURF REM & RESURF
	114	14	1596	177	HMA	HMA SURF REM & RESURF
SB I-55 @ LAGRANGE RD - NB EXIT RAMP	18	12	216	24	HMA	HMA SURF REM & RESURF
NB I-55 @ 1ST AVENUE - SB EXIT RAMP	12	12	144	16	HMA	HMA SURF REM & RESURF
	12	12	144	16	HMA	HMA SURF REM & RESURF
NB I-55 @ CICERO AVE - ENTRANCE RAMP	44	12	528	59	HMA	HMA SURF REM & RESURF
	12	12	144	16	HMA	HMA SURF REM & RESURF
	18	12	216	24	HMA	HMA SURF REM & RESURF
SB I-55 @ CICERO AVE - EXIT RAMP	12	12	144	16	HMA	HMA SURF REM & RESURF
SB-I-55 @ CICERO AVE - ENTRANCE RAMP	23	12	276	31	HMA	HMA SURF REM & RESURF
	16	12	192	21	HMA	HMA SURF REM & RESURF
SB I-55 @ PULASKI ROAD - EXIT RAMP	12	12	144	16	HMA	HMA SURF REM & RESURF
	10	12	120	13	HMA	HMA SURF REM & RESURF
	10	12	120	13	HMA	HMA SURF REM & RESURF
	12	12	144	16	HMA	HMA SURF REM & RESURF
	12	12	144	16	HMA	HMA SURF REM & RESURF
SB I-55 @ PULASKI ROAD - ENTRANCE RAMP	12	12	144	16	HMA	HMA SURF REM & RESURF
	12	12	144	16	HMA	HMA SURF REM & RESURF
NB I-55 @ STATE STREET - ENTRANCE RAMP	12	15	180	20	PCC	CLASS D PATCH
SB I-55 @ STATE STREET - EXIT RAMP	12	12	144	16	PCC	CLASS D PATCH
SB LAKE SHORE DRIVE RAMP TO SB I-55	752	22	16544	1838	HMA	HMA SURF REM & RESURF

NB I-55 @ PULASKI ROAD - ENTRANCE RAMP	24	12	288	32	HMA	HMA SURF REM & RESURF
NB I-55 @ HARLEM AVE - EXIT RAMP	4	12	48	5	HMA	HMA SURF REM & RESURF
	4	12	48	5	HMA	HMA SURF REM & RESURF
NB I-55 @ CALIFORNIA AVE - EXIT RAMP	24	3	72	8	PCC	CLASS D PATCH

(7-18-08)

Rev. 7-22-08

FILE NAME *	USER NAME * s1greendp	DESIGNED -	REVISED - 7/15/08 - DPW	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
en\projects\136588\design.ee.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	VAR.	2008-050 PP	COOK	18	5
		CHECKED -	REVISED -												
		DATE -	REVISED -												
PLOT SCALE = 100.0000' / IN.															
PLOT DATE = 7/15/2008															
FED. ROAD DIST. NO.												ILLINOIS FED. AID PROJECT			

LOCATIONS FOR INTERSTATE 290	REPAIR LENGTH (FT)	REPAIR WIDTH (FT)	REPAIR AREA (SF)	REPAIR AREA (SY)	SURFACE TYPE	REPAIR WORK
EB I-290 EXIT RAMP TO PAULINA AVENUE	5	12	60	7	HMA	HMA SURF REM & RESURF
EB I-290 RAMP TO NB KENNEDY EXPY	5	12	60	7	HMA	HMA SURF REM & RESURF
	4	12	48	5	HMA	HMA SURF REM & RESURF
NB DAN RYAN EXPY TO WB I-290	4	12	48	5	HMA	HMA SURF REM & RESURF
	4	12	48	5	HMA	HMA SURF REM & RESURF
	8	12	96	11	HMA	HMA SURF REM & RESURF
NB DAN RYAN RAMP CONC SECT TO BRIDGE ABUTMENT	300	16	4800	533	HMA	HMA SURF REM & RESURF
BRIDGE ABUTMENT TO GORE AREA NW QUADRANT	400	16	6400	711	HMA	HMA SURF REM & RESURF

WB I-290 ENTRANCE RAMP FROM INDEPENDENCE AVE	12	12	144	16	HMA	HMA SURF REM & RESURF
--	----	----	-----	----	-----	-----------------------



LOCATIONS FOR OHIO STREET FEEDER	REPAIR LENGTH (FT)	REPAIR WIDTH (FT)	REPAIR AREA (SF)	REPAIR AREA (SY)	SURFACE TYPE	REPAIR WORK
EASTBOUND OHIO STREET FEEDER RAMP	470	VARIES	24444	2716	HMA	HMA SURF REM & RESURF MAINLINE ONLY - NO SHLDS
WESTBOUND OHIO STRET FEEDER RAMP	465	VARIES	16929	1881	HMA	HMA SURF REM & RESURF MAINLINE ONLY - NO SHLDS
<b>NOTE: USE POLYMERIZED HMA SURFACE COURSE, MIX "F", N90 AT THESE LOCATIONS</b>						

(7-15-08)

Rev. 7-22-08

FILE NAME *	USER NAME = wilgreenp	DESIGNED -	REVISED - 7/15/08 - DPW
d:\projects\136588\design.ee.dgn		DRAWN -	REVISED -
PLOT SCALE = 1/8" = 100'		CHECKED -	REVISED -
PLOT DATE = 7/15/2008		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-050 PP	COOK	18	6
CONTRACT NO. 60E99				