



F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00017-00-PV	KANE	232	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

SPECIALTY ITEMS	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	QUANTITY	80 % FEDERAL 20% VILLAGE					Y060 100% VILLAGE
					1000-2A	Y002 - TRAFFIC SIGNS	Y030 - /E HIGHWAY LIGHTING	Y031 - /F TRAFFIC SIGNALS	Y046 - BICYCLE & PEDESTRIAN FACILITY	
	73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	3		3				
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1994	1994					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30504	30504					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	10591	10591					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1446	1446					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	520	520					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	357	357					
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10					
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2					
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1730	1730					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	300	300					
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1			
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1			
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	2134				2134		
*	81000700	CONDUIT IN TRENCH, 2-1/2" DIA., GALVANIZED STEEL	FOOT	590				590		
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	292			240	52		
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	212				212		
*	81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	34				34		
*	81018500	CONDUIT, PUSHED 2" DIA., GALVANIZED STEEL	FOOT	522				522		
*	81018600	CONDUIT, PUSHED 2-1/2" DIA., GALVANIZED STEEL	FOOT	301			190	111		
*	81018900	CONDUIT, PUSHED 4" DIA., GALVANIZED STEEL	FOOT	1298			306	992		
*	81400100	HANDHOLE	EACH	10				10		
*	81400200	HEAVY-DUTY HANDHOLE	EACH	7				7		
*	81400300	DOUBLE HANDHOLE	EACH	4				4		
*	81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	4469				4469		
	81701345	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C NO. 3/0	FOOT	280				280		
*	81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	800				800		
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3715				500	3215	
*	82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	4				4		
*	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	22				22		
*	82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1				1		
*	83050730	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 8 FT. DAVIT ARM	EACH	8				8		
*	83050800	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 12 FT. MAST ARM	EACH	14				14		
*	83057220	LIGHT POLE, WOOD, 40 FOOT, CLASS 4	EACH	2				2		
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	180				180		
*	83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	40				40		
*	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	22				22		
*	84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	2				2		
*	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	2				2		
*	84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	6				6		
*	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1				1		
*	84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1				1		
*	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1				1		
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1				1		

PLAN	REVISIONS	DATE
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	

PROFILE	REVISIONS	DATE
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	
NO.	BY	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS
DATE: 02/07/08

DRAWN BY:
CHECKED BY: WBR