



F.A. N/A	SECTION 06-00017-00-PV	COUNTY KANE	TOTAL SHEETS 232	SHEET NO. 9
STA. TO STA.			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	

SUMMARY OF QUANTITIES

SPECIALTY ITEMS	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	QUANTITY	80 % FEDERAL 20% VILLAGE						
					1000 - 2A	Y002 - TRAFFIC SIGNS	Y030 - /E HIGHWAY LIGHTING	Y031 - /F TRAFFIC SIGNALS	Y046 - BICYCLE & PEDESTRIAN FACILITY	Y080 - TRAINING	Y060 100% VILLAGE
*	85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1				1			
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2388				2388			
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4647				4647			
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	4851				4851			
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	7540				7540			
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	337				337			
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	8				8			
*	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1				1			
*	87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1				1			
*	87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1				1			
*	87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1				1			
*	87700320	STEEL MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1				1			
*	87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1				1			
*	87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	3				3			
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	36				36			
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8				8			
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	120				120			
*	87900200	DRILL EXISTING HANDHOLE	EACH	1				1			
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	12				12			
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	10				10			
*	88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2				2			
*	88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	6				6			
*	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED ALUMINUM	EACH	22				22			
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	30				30			
*	88600100	DETECTOR LOOP, TYPE I	FOOT	4122				4122			
*	88700200	LIGHT DETECTOR	EACH	9				9			
*	88700300	LIGHT DETECTOR AMPLIFIER	EACH	4				4			
*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1				1			
*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5432				5432			
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1				1			
*	89502380	REMOVE EXISTING HANDHOLE	EACH	7				7			
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		2		7			
*	X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	6491				6491			
*	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	4			4				
*	X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1				1			
*	X0502600	TEMPORARY LIGHTING	L SUM	1			1				
*	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	166	166						
*	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	2				2			
*	X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	6491				6491			
*	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2458				2458			
*	X8730250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 20 3/C, TWISTED, SHIELDED	FOOT	2562				2562			
*	XX000836	PRESSURE TESTING AND DISINFECTION	L SUM	1							1
*	XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	2876							2876
*	XX003787	FIRE HYDRANT ASSEMBLY & VALVE	EACH	7							7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS
DATE: 02/07/08

DRAWN BY:
CHECKED BY: WBR

PLAN

SURVEYED
ALIGNMENT CHECKED
RT. OF WAY CHECKED
CADD FILE NAME

BY: _____ DATE: _____

NOTE BOOK NO. _____

PROFILE

SURVEYED
GRADES
E.M. NOTED
STRUCTURE NOTATIONS OK'D

BY: _____ DATE: _____

NOTE BOOK NO. _____