



F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00017-00-PV	KANE	232	10
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

SPECIALTY ITEMS	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	QUANTITY	80 % FEDERAL 20% VILLAGE						
					1000-2A	Y002 - TRAFFIC SIGNS	Y030 - /E HIGHWAY LIGHTING	Y031 - /F TRAFFIC SIGNALS	Y046 - BICYCLE & PEDESTRIAN FACILITY	Y080 - TRAINING	Y060 100% VILLAGE
	XX003919	FLAGPOLE RELOCATION	L SUM	1	1						
	XX004096	REMOVE AND RE-INSTALL CONCRETE FLARED END SECTIONS	EACH	7	7						
	* XX004731	CONNECTION TO EXISTING WATERMAIN	EACH	4							4
	* XX004907	GATE VALVE 12" WITH VAULT, 5' DIAMETER	EACH	8							8
	* X0325705	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1				1			
	* XX005084	LIGHTING CONTROLLER FOUNDATION	EACH	1			1				
	* XX005106	PVC CASING PIPE, 18"	FOOT	25							25
	* XX005401	STEEL CASING PIPE 24" (BORED AND JACKED)	FOOT	365							365
	* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	2				2			
	* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	20			20				
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	34,661	34,661						
	Z0002750	BARRICADES, TYPE III	EACH	9	9						
	Z0076600	TRAINEES	HOUR	3,500						3,500	
	* XX007558	GATE VALVE 6" WITH VAULT, 4' DIAMETER	EACH	1							1
	* XX007559	GATE VALVE 8" WITH VAULT, 4' DIAMETER	EACH	1							1
	* XX007560	SANITARY SEWER, PVC SDR-21, 10"	FOOT	815							815
	* XX007561	SANITARY SEWER, PVC SDR-21, 12"	FOOT	545							545
	XX007562	SIGN REMOVAL, SPECIAL	L SUM	1			1				
	X0324879	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	4	4						
	* XX007563	TEMPORARY LUMINAIRE, SODIUM VAPOR HORIZONTAL MOUNT 310 WATT WITH PHOTOCCELL	EACH	4				4			
	* XX007564	TEMPORARY LUMINAIRE, SODIUM VAPOR HORIZONTAL MOUNT 400 WATT WITH PHOTOCCELL	EACH	4				4			
	* XX007565	POLYETHYLENE DUCT BORED AND PULLED, 1 1/4" DIA WITH ELECTRIC CABLE 600 V (EPR-TYPE RHW) 3-1/C NO. 6 AND 1/C NO. 6 GROUND	FOOT	5,350				5,350			
	XX007566	STORM SEWER REMOVAL AND REINSTALLATION, 15"	FOOT	25	25						

PLAN	DATE
BY	
SURVEYED	
ALIGNED	
NOTED	
CHECKED	
RT. OF WAY	
CHECKED	
NO.	
FILE NAME	

PROFILE	DATE
BY	
SURVEYED	
ALIGNED	
NOTED	
CHECKED	
STRUCTURE	
NOTATIONS	
GRID	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS
DATE: 02/07/08

DRAWN BY:
CHECKED BY: WBR