CONTRACT NO. 63023

Engineering Enterprises, Inc.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00017-00-PV	KANE	232	29
STA.		TO STA.		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

STRUCTURE SCHEDULE

STR.	STATION	OFFSET	LT./RT.	INLET TY A TY 11V F&G	INLET TY B TY 11V F&G	INLET TY A TY 24 F&G	INLET TY B TY 24 F&G	CB TY A 4' DIA TY 11 F&G	CB TY A 4' DIA TY 24 F&G	CB TY C 2' DIA TY 11V F&G	CB TY C 2' DIA TY 24 F&G	MH TY A 4' DIA TY 1 FR&CL	MH TY A 4' DIA TY 8 F&G	MH TY A 4' DIA TY 11V F&G	MH TY A 4'DIA TY 24 F&G	MH TY A 5' DIA TY 1 FR&CL	MH TY A 6' DIA TY 1 FR&CL	REM & REL FES	PRC FES 12"	PRC FES 18"	PRC FES 24"	PRC FES 36"	STONE RIPRAP CLASS A3			STRUCTURE INVERTS					RIM ELEV
				EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	LENGTH FOOT	WIDTH FOOT	AREA SQ. YD.	N	S	E	W		
100	5411.8	105.4	LT																	1			12	6	8			701.70			N/A
100A	5411.8	47.5	LT						1																		701.85	701.85	701.85		706.06
100B	5399.3	47.5	LT			1																				701.90					705.91
100C	5411.8	35.5	RT				1																				702.30		702.30		706.12
100D	5399.3	35.5	RT			1																				702.40					706.13
101	5480.1	95.0	LT																	1			12	6	8					NE 701.70	N/A
101A	5530.0	46.6	LT						1																			702.10		SW 702.10	707.82
101B	5530.0	4.5	RT											1												702.35	702.35	702.35	702.35		706.88
101C	5530.0	35.5	RT				1																						702.60	NE 702.60	706.63
101D	5465.1	4.5	RT	1																						702.65					706.75
101E	5583.6	4.5	RT		1																					703.80	703.80				707.28
101F	5636.8	4.3	RT	1																							704.05				707.61
102	5689.6	44.0	RT									1														703.65	703.65		703.65		708.35
102A	5689.6	35.5	RT				1																					703.75	703.75		707.75
102B	5689.6	1.2	RT		1																					704.10		704.10			708.35
102C	5724.4	0.9	LT	1																							704.45				708.50
103	5837.7	44.0	RT									1														704.65	704.65		704.65		708.95
103A	5837.7	35.5	RT				1																					704.70	704.70		708.16
103B	5837.8	7.5	LT	1																								705.05			708.40
104	5965.0	44.0	RT									1														705.20	705.20		705.20		709.35
104A	5965.0	35.5	RT				1																					705.25	705.25		708.80
104B	5965.0	7.5	LT	1																								705.65			709.04
105	5469.8	177.5	LT																	1			12	6	8					NW 701.70	N/A
105A	5518.0	205.2	LT																	1										SE 701.90	N/A
106	6129.9	44.0	RT									1															705.90		705.90		710.55
106A	6129.9	9.0	RT					1																				706.05	706.05		710.55
106B	6130.1	33.0	LT			1																						706.25			710.30
600	22167.8	369.1	RT																			1	16	9	16					NW 700.70	
601	22156.5	339.9	RT													1										700.80				SE 700.80	710.00
602	22157.8	70.8	RT														1									701.30	701.30	701.30	701.30		710.85
602A	22157.8	61.2	LT										1														702.30				710.85
603	22010.0	70.6	RT									1														706.25		706.25			711.50
603A	22010.0	35.5	RT						1																	706.45	706.45				710.80
603B	22010.0	35.5	LT			1																					706.75				710.80
604	22570.2	372.5	RT																		1									NE 700.43	N/A
605	22670.9	334.5	RT													1										700.24			700.24		709.50
606	22603.1	152.9	RT													1										699.91				SE 699.91	709.50
700	5357.0	103.2	LT																	1			12	6	8					SE 701.70	N/A
701	5300.0	47.5	LT						1																			701.95		NW 701.95	706.66
702	5300.0	37.8	RT				1																					702.20	702.20		706.80
703	5310.0	82.3	RT																	1									702.35		N/A
704	5300.0	250.1	LT																1				12	6	8	701.52					N/A
704A	5330.0	250.8	LT													1										701.63	701.63				707.50
704B	5353.2	251.2	LT																1								701.70				N/A
801	22340.0	71.0	RT									1														704.70		702.65	702.65		710.05
801A	22340.0	30.2	RT						1																	704.90	704.90				709.20
	SUBTOTALS			5	2	4	6	1	5	0	0	6	1	1	0	4	1	0	2	5	1	1			56						

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STRUCTURE SCHEDULE

SCALE: NTS

DRAWN BY:

DATE: 02/07/08

CHECKED BY: WBR

PLAN | NOTE BOOK NO. ____ | SURVEYED ____ PLOTTED ____ ALIGNMENT CHECKED ____ RT. OF WAY CHECKED ____ CADD FILE NAME ____ | BY | DATE

PROFILE | NOTE BOOK NO. ____ | SURVEYED ____ PLOTTED ____ GRADES CHECKED ____ B.M. NOTED ____ STRUCTURE NOTATNS CHKD ____ | BY | DATE

Plotted: May 27, 2008 @ 3:05 PM By: Kris Pung - Tab: 29 SCH-4 (22x34)

Path: H:\SDSKPROJ\SGD548\DWG\SG0722\DWG FINAL ENG\CONTRACT B\B-SGD548-SCHEDS