CONTRACT NO. 63023

Engineering Enterprises, Inc.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	N/A	06-00017-00-PV	KANE	232	31
	STA.		TO STA.		
	FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

STRUCTURE SCHEDULE

STR.	STATION	OFFSET	LT./RT.	INLET TY A TY 11V F&G	INLET TY B TY 11V F&G	INLET TY A TY 24 F&G	INLET TY B TY 24 F&G	CB TY A 4' DIA TY 11 F&G	CB TY A 4' DIA TY 24 F&G	CB TY C 2' DIA TY 11V F&G	CB TY C 2' DIA TY 24 F&G	MH TY A 4' DIA TY 1 FR&CL	MH TY A 4' DIA TY 8 F&G	MH TY A 4' DIA TY 11V F&G	MH TY A 4'DIA TY 24 F&G	MH TY A 5' DIA TY 1 FR&CL	MH TY A 6' DIA TY 1 FR&CL	REM & REL FES	PRC FES 12"	PRC FES 18"	PRC FES 24"	PRC FES 36"	STONE RIPRAP CLASS A3			STRUCTURE INVERTS					RIM ELEV
				EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	LENGTH FOOT	WIDTH FOOT	AREA SQ. YD.	N	S	E	W		
1202A	23315.3	4.5	LT							1																	708.20				711.45
1203	23349.5	35.7	RT																1							708.08					N/A
1203A	23349.5	24.4	RT								1																708.20				710.90
1204	23467.0	30.6	RT																1							708.27					N/A
1204A	23467.0	20.0	RT								1																708.40				710.80
1205	23500.0	28.8	RT																1							708.33					N/A
1205A	23500.0	18.7	RT								1																708.40				710.70
1206	23591.0	24.8	RT																1							708.50					N/A
1206A	23591.0	15.3	RT								1																708.60				710.65
1207	23823.8	8.0	RT						1																	707.50		707.50	707.50		710.95
1208	23700.0	20.4	RT						1																		708.05	708.05	708.05		710.55
1208A	23700.0	11.2	RT																1							708.10					N/A
1209	23685.1	11.7	RT			1																						708.15			710.55
1210	23957.7	7.5	RT												1													707.95	707.95		712.30
1211	24032.7	7.5	RT				1																					708.50	708.50		712.65
1212	24207.7	7.5	RT			1																							709.70		713.75
1213	24900.0	1.5	RT								1																710.65				713.00
1213A	24900.0	5.1	LT																1							710.55					N/A
1214	23818.9	64.3	LT																1				12	6	8				707.00		N/A
1215	23740.8	64.3	LT	1																								707.34	707.34		710.02
1216	23704.1	64.3	LT	1																								707.49	707.49		710.22
1217	23581.4	64.3	LT	1																								708.04	708.04		710.32
1218	23548.6	64.3	LT	1																								708.17	708.17		710.22
1219	23466.9	64.3	LT	1																								708.45	708.45		710.52
1220	23444.1	64.3	LT	1																								708.52	708.52		710.47
1300	29877.4	69.2	LT																1											NE 708.1	N/A
1300A	29899.1	10.5	LT							1																				SW 708.4	714.65
1301	30278.5	66.9	LT																1									707.50			N/A
1301A	30278.5	10.5	RT							1																			707.90		713.25
1302	30611.1	64.3	LT																1									706.99			N/A
1302A	30611.1	1.5	LT							1																			707.35		712.25
1303	30232.5	44.5	RT							1																		708.35			712.32
1303A	30233.2	66.0	RT																1										708.24		N/A
		SUBTOTALS		6	0	2	1	0	2	5	5	0	0	0	1	0	0	0	11	0	0	0			8						
		TOTAL		11	5	13	8	2	11	11	6	12	3	4	2	5	1	7	16	5	2	1			124						

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STRUCTURE SCHEDULE

SCALE: NTS

DRAWN BY:

DATE: 02/07/08

CHECKED BY: WBR

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / RT. OF WAY CHECKED / CADD FILE NAME / NOTE BOOK NO. / BY / DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / B.M. NOTED / STRUCTURE NOTAT'NS CH'KD / NOTE BOOK NO. / BY / DATE

Plotted: May 27, 2008 @ 3:06 PM By: Kris Furig - Tab: 31 SCH-6 (22x34)

Path: H:\SGSKPROJ\SG0546\DWG\SG0732\DWG FINAL ENG\CONTRACT BYB-SG0546-SCHEDS