

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	11BR-1	*	43	3
STA.		TO STA.		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				
* WHITESIDE & ROCK ISLAND				

Item No.	Item	Unit	80% FED / 20% STATE Total	ROCK ISLAND COUNTY I000 ROADWAY	WHITESIDE COUNTY I000 ROADWAY	WHITESIDE COUNTY X020-2A BRIDGE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	--	6	--
20200100	EARTH EXCAVATION	CU YD	51	19	32	--
20300100	CHANNEL EXCAVATION	CU YD	26	--	26	--
20400800	FURNISHED EXCAVATION	CU YD	914	278	636	--
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	66	--	--	66
25000750	MOWING	ACRE	0.9	0.4	0.5	--
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	145	65	80	--
28000300	TEMPORARY DITCH CHECKS	EACH	1	1	--	--
28000400	PERIMETER EROSION BARRIER	FOOT	1000	525	475	--
28000500	INLET AND PIPE PROTECTION	EACH	1	--	1	--
28100107	STONE RIPRAP, CLASS A4	SQ YD	438	--	--	438
28200200	FILTER FABRIC	SQ YD	438	--	--	438
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	460	263	197	--
35101400	AGGREGATE BASE COURSE, TYPE B	TON	86	22	64	--
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.5	--	2.5	--
40600525	LEVELING BINDER (HAND METHOD), N50	TON	3	1.5	1.5	--
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	173	94	79	--
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N50	TON	246	75	171	--
40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SQ YD	692	391	301	--
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	222	111	111	--
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	627	280	347	--
44000700	APPROACH SLAB REMOVAL	SQ YD	114	57	57	--
44004300	PAVEMENT BREAKING	SQ YD	905	498	407	--
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	900	461	439	--
48101200	AGGREGATE SHOULDERS, TYPE B	TON	547	218	329	--
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	--	--	1
50200100	STRUCTURE EXCAVATION	CU YD	110	--	--	110
50300100	FLOOR DRAINS	EACH	12	--	--	12
50300225	CONCRETE STRUCTURES	CU YD	118.0	--	--	118.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	228.8	--	--	228.8
50300260	BRIDGE DECK GROOVING	SQ YD	336	--	--	336
50300300	PROTECTIVE COAT	SQ YD	673	111	111	451
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	47660	--	--	47660
51201300	FURNISHING STEEL PILES HP8X36	FOOT	551	--	--	551
51201600	FURNISHING STEEL PILES HP12X53	FOOT	537	--	--	537

PLOT DATE = 10/07  
 FILE NAME = Z09805SUMQUANT  
 PLOT SCALE = NONE  
 USER NAME = CHANS

100% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 FAS 203 (MOLINE ROAD)  
 SECTION 11BR-1  
 WHITESIDE & ROCK ISLAND COUNTIES

SCALE: VERT.  
 HORIZ.  
 DATE 12/05

DRAWN BY ARR  
 CHECKED BY JKC