

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	I 000 - 2A 100% STATE
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	294.00	294.00
△ 40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	21.50	21.50
40600300	AGGREGATE (PRIME COAT)	TON	57.00	57.00
40600555	LEVELING BINDER (HAND METHOD), N105	TON	208.10	208.10
△ 40600655	LEVELING BINDER (MACHINE METHOD), N105	TON	2,144.00	2,144.00
40600895	CONSTRUCTING TEST STRIP	EACH	1.00	1.00
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	432.00	432.00
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	134.00	134.00
40600990	TEMPORARY RAMP	SQ YD	2,173.00	2,173.00 △
△ 40603375	HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	3,441.0	3,441.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	4,879.00	4,879.00
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	100.00	100.00
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SQ YD	331.00	331.00
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1.00	1.00
64200105	SHOULDER RUMBLE STRIP	FOOT	13,245.00	13,245.00
67100100	MOBILIZATION	L SUM	1.00	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	7.00	7.00

△ REVISED 7-23-08

FILE NAME = P:\1-00 resur-favr.dgn	USER NAME = grantpm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	80	*	ROCK ISLAND	31	3
		CHECKED -	REVISED -						CONTRACT NO. 64034						
		DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT										