

SUMMARY OF QUANTITIES				80% FEDERAL 20% STATE	
PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	I000 ROADWAY	SFTY-2A SN 027-2007
20400800	FURNISHED EXCAVATION	CU YD	44	44	
* 25000200	SEEDING, CLASS 2	ACRE	0.21	0.21	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	19	19	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	19	19	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	19	19	
* 25100630	EROSION CONTROL BLANKET	SQ YD	1,055	1,055	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	257	257	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15,411	15,409.3	1.7
40600300	AGGREGATE (PRIME COAT)	TON	386	385.7	0.3
40600400	MIXTURE FOR CRACKS, JOINT AND FLANGEWAYS	TON	56	56	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	94	94	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	7,869	7,863	6
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	487	487	
40600990	TEMPORARY RAMP	SQ YD	491	491	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	15,739	15,727	12
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	487	487	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	34,949	34,949	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	152,137	152,003.7	133.3
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	4,988	4,988	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	328	328	
44201777	CLASS D PATCH, TYPE II, 11 INCH	SQ YD	1,403	1,403	
44201781	CLASS D PATCH, TYPE III, 11 INCH	SQ YD	1,287	1,287	
44201783	CLASS D PATCH, TYPE IV, 11 INCH	SQ YD	497	497	
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	6,918	6,913	5
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	9	9	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	LSUM	1	1	

SUMMARY OF QUANTITIES				80% FEDERAL 20% STATE	
PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	I000 ROADWAY	SFTY-2A SN 027-2007
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	LSUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16,113	16,113	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62.4	62.4	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	136,164	136,164	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	11,792	11,792	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	276	276	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	331	331	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,772	1,772	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62.4	62.4	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20,228	20,228	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	868	868	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	276	276	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	331	331	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	139	139	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	115,936	115,936	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	10,924	10,924	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	262	262	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,098	1,098	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,098	1,098	
# 20076600	TRAINEES	HR	1,000	1,000	

\* SPECIALTY ITEMS  
# Y080

FILE NAME =	USER NAME = duncenbd	DESIGNED -	REVISED - DIST. 3 COMMENTS
c:\projects\ed02464\consult\ed02464.dwg	ahsqy@ldgn	DRAWN - MAP	REVISED - 5/29/04
	PLOT SCALE = 1:8000 / 1" = 80'	CHECKED - RRM	REVISED - BDD 02/05/08
	PLOT DATE = Mar 11, 2008 - 08:45:28 AM	DATE - 02/26/04	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 326	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		FORD	22	3
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT CONTRACT NO. 66423				

\*(125)RS-5, (126)RS-3 & (127)RS-2