

		1000		
		100% State		
PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL	TOTAL
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10.8	10.8
40600300	AGGREGATE (PRIME COAT)	TON	42.9	42.9
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	250.0	250.0
40600990	TEMPORARY RAMP	SQ YD	83.3	83.3
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,801.1	1,801.1
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	28,096.9	28,096.9
48203100	HOT-MIX ASPHALT SHOULDERS	TON	580.0	580.0
52000320	NEOPRENE EXPANSION JOINT 2"	FOOT	242.0	242.0
67100100	MOBILIZATION	LSUM	1.0	1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,400.0	1,400.0
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	250.0	250.0
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	17,746.0	17,746.0



Rev. 7-16-08

FILE NAME = C:\Projects\603406\shitsq.dgn	USER NAME = [eugh]jrr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 315	SECTION 23 RS-2	COUNTY HANCOCK	TOTAL SHEETS 15	SHEET NO. 3			
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	SCALE:			SHEET NO. 3 OF 15 SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT				
PLOT DATE = Jul-09-2008 11:59:45AM	DATE -	REVISED -											