

PAY CODE	ITEM DESCRIPTION	UNIT	1000	
			100% State	TOTAL
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10.8	10.8
40600300	AGGREGATE (PRIME COAT)	TON	42.9	42.9
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	250.0	250.0
40600990	TEMPORARY RAMP	SQ YD	83.3	83.3
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,801.1	1,801.1
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	28,096.9	28,096.9
48203100	HOT-MIX ASPHALT SHOULDERS	TON	580.0	580.0
67100100	MOBILIZATION	LSUM	1.0	1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,400.0	1,400.0
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	250.0	250.0
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	17,746.0	17,746.0

FILE NAME = C:\Projects\4603408\shitsq.dgn

USER NAME = laughlin
 PLOT SCALE = 100.0000' / IN.
 PLOT DATE = Jul-09-2008 11:59:45AM

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 15 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	23 RS-2	HANCOCK	15	3
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				

CONTRACT NO. 72C31