

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE - SFTY2A - 100% STATE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	SN 060-0120 ILL 111 over Bloomer & Rodgers Ave. Madison Co.	SN 003-0015 US 40 over I-70 EB/WB Bond Co.	SN 082-0166 ILL 111 over I-64 EB/WB St. Clair Co.	SN 082-0051 & 082-0052 ILL 15 EB/WB over ILL 13 St. Clair Co.
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4		2	2	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.33	0.33	0.34	
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	0.33	0.33	0.34	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1				1
50157301	PROTECTIVE SHIELD (PERMANENT)	SQ YD	2250	855	581	434	380

INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS, SUMMARY OF QUANTITIES, GENERAL NOTES, STANDARDS
3. LOCATION MAPS
4. SN 060-0120 (ILL 111 OVER BLOOMER AVE. & RODGERS AVE.)
5. SN 003-0015 (US 40 OVER I-70 EB/WB)
6. SN 082-0166 (ILL 111 OVER I-64 EB/WB)
7. SN 082-0051 & SN 082-0052 (ILL 15 EB/WB OVER ILL 13)
8. PROTECTIVE SHIELDING DETAILS

GENERAL NOTES

Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work; however, the Contractor will be paid for the quantity actually furnished at the unit price for the work.

Field welding of construction accessories will not be permitted to beams or girders.

All lanes on the structures shall be kept open to traffic.

The protective shielding plywood shall be cut to miss all crossframes or diaphragms that interfere. All gaps between plywood and crossframes or diaphragms shall be less than 1/2".

Utility Interferences are not anticipated on this contract. Should this prove to be otherwise during any time of the construction, no additional cost shall be added to the contract resulting from the occurrence. The Joint Utility Locating Information for Excavators (J.U.L.I.E.) System number is (800) 892-0123.

Protective shielding shall extend to the outer edges of the shoulders, but sections may extend further as shown on the plans due to bridge skew. A two-week notice shall be given to the Resident Engineer prior to all lane closures.

STANDARDS

701400-02
701406-04
701411-04
701446
701501-04
701901

* Dist 8 Bridge Rehab 2009-1

FILE NAME =	USER NAME = #USER#	DESIGNED - BJW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, SUMMARY OF QUANTITIES, GENERAL NOTES, STANDARDS	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - BJW	REVISED -			VAR.			VARIOUS	8	2
	PLOT SCALE = #SCALE#	CHECKED - JAU	REVISED -			CONTRACT NO. 76890					
	PLOT DATE = #DATE#	DATE - 01/16/08	REVISED -			SCALE:	SHEET NO. 2 OF 8 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT