

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	22	13

STA. _____ TO STA. _____
 FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT

- * FAS 1909 & FAP 322
- ** D9 PAVEMENT PRESERVATION FY08
- *** JACKSON AND UNION COUNTIES

FAS 1909 (IL 127) PAVEMENT MARKING SCHEDULE
 LOCATION 3

STATION TO STATION	PAINT PAVEMENT MARKING			TEMPORARY	NOTES
	4 INCH WHITE	4 INCH YELLOW	4 INCH SKIP-DASH YELLOW	4 INCH	
	FOOT	FOOT	FOOT	FOOT	
IL 127 - STA. 335+53 TO STA. 227+32					
LT & RT 335+53.0 TO 344+07.4	1,709			1,709	Edge Line
EQ STA 344+07.4 (BK.) = STA. 6+06.7 (AH.)					
LT & RT 6+06.7 TO 79+77.7	14,742			14,742	Edge Line
EQ STA 79+77.7 (BK.) = STA. 80+07.7 (AH.)					
LT & RT 80+07.7 TO 138+96.2	11,777			11,777	Edge Line
EQ STA 138+96.2 (BK.) = STA. 139+83.1 (AH.)					
LT & RT 139+83.1 TO 227+32.0	17,498			17,498	Edge Line
LT 335+53.0 TO 22+71.2		2,519		2,519	No Passing Zone
LT 31+76.9 TO 131+96.1		9,989		9,989	No Passing Zone
LT 142+64.7 TO 186+77.4		4,413		4,413	No Passing Zone
LT 195+93.5 TO 227+32.0		3,139		3,139	No Passing Zone
RT 335+53.0 TO 12+72.7		1,520		1,520	No Passing Zone
RT 23+05.5 TO 118+55.0		9,520		9,520	No Passing Zone
RT 128+73.6 TO 176+59.3		4,699		4,699	No Passing Zone
RT 185+92.2 TO 227+32.0		4,140		4,140	No Passing Zone
12+72.0 TO 31+76.9			476	476	
118+55.0 TO 128+73.6			255	255	
131+96.2 TO 142+64.7			982	982	
176+59.3 TO 185+92.2			933	933	
186+77.4 TO 195+93.5			916	916	
SUB-TOTALS	45,726	39,939	3,562	89,227	
TOTALS		89,227		89,227	

PLOT DATE = 12/27/2007
 FILE NAME = c:\wps\pave\1801z\mascdp
 USER NAME = masonr