

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.S. 321	05-00205-02-RS	IROQUOIS	76	3
FED. ROAD DIST. NO.		ILLINOIS	CONTRACT NO. 87363	

SUMMARY OF QUANTITIES			
C.CODE #	ITEM	UNIT	TOTAL QUANTITY
			I 000
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	97
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4846
40600300	AGGREGATE (PRIME COAT)	TON	94
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	4604
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	199
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	448
40600990	TEMPORARY RAMP	SQ YD	328
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3976
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	174
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	50
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	160
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	200
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1381
48203010	HOT-MIX ASPHALT SHOULDERS, 3 1/4"	SQ YD	4681
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	450
* ^ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	212.5
^ 66700110	PERMANENT SURVEY MARKERS TO BE ADJUSTED	EACH	7
^ 67100100	MOBILIZATION	L SUM	1
^ 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10998
* 70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	45639
* 70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	95
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18878
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	45639
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	95
* ^ 78200405	GUARDRAIL MARKERS	EACH	10
* ^ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4

^ SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEMS

PLOT DATE : 5/16/2008 FILE NAME = 46002-shr-summary.dgn

<b>HAMPTON, LENZINI &amp; RENWICK, INC.</b> CIVIL & STRUCTURAL ENGINEERS LAND SURVEYORS 	
3085 STEVENSON DRIVE, SUITE 201 SPRINGFIELD, ILLINOIS 62703 (217) 546-3400	
ELGIN	SPRINGFIELD
PROJECT NUMBER: 07.0120.320	DATE: 05/06/08
DESIGNED: L.F.S.	CHECKED: DRAWN: W.J.S.

**SUMMARY OF QUANTITIES**  
**F.A.S. 321 / C.H. 4**  
**SECTION 05-00205-02-RS**  
**IROQUOIS COUNTY**