

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.S. 321	05-00205-02-RS	IROQUOIS	76	4
FED. ROAD DIST. NO.		ILLINOIS	CONTRACT NO. 87363	

LOCATION	ROADWAY SCHEDULE										
	HOT-MIX ASPHALT SURFACE CSE MIX "C", N50 1.5"	LEVELING BINDER (MM) N50 1.75"	HOT-MIX ASPHALT SURFACE REMOVAL BUTT-JOINT	PCC SURFACE REMOVAL BUTT-JOINT	TEMPORARY RAMP	BITUMINOUS MATERIAL PRIME COAT	AGGREGATE PRIME COAT	HOT-MIX ASPHALT SHOULDERS 3.25"	AGGREGATE SHOULDER WEDGE TYPE B	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SURFACE COURSE TYPE B 6"
	TON	TON	SQ YD	SQ YD	SQ YD	GAL	TON	SQ YD	TON	TON	TON
STA. 4+85 TO STA. 17+95.01	299	374		106	66	351	7	2906	48		
STA. 20+54.27 TO STA. 46+18	577	862		53	53	684	14	1444	164		
STA. 46+18 TO STA. 190+75	2972	3323	49		52	3535	71		1147		
RAMPS A & C (SOUTH)	62	22		117	29	68	1	153	11		
RAMPS B & D (NORTH)	66	23		172	41	73	1	178	11		
SIDE ROADS			126		63	76				118	
ENTRANCES			24		24	59				56	97
TOTAL	3976	4604	199	448	328	4846	94	4681	1381	174	97

LOCATION	PAVEMENT MARKING SCHEDULE									
	PAINT								SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
	PERMANENT				TEMPORARY					
	4" SINGLE WHITE EDGE LINE	4" SKIP DASH YELLOW CENTERLINE	4" SOLID YELLOW CENTERLINE	24" WHITE STOP BAR	4" SINGLE WHITE EDGE LINE	4" SKIP DASH YELLOW CENTERLINE	4" SOLID YELLOW CENTERLINE	24" WHITE STOP BAR	4" SKIP DASH YELLOW CENTERLINE	
FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	
CH4										
CL STA. 4+85 TO CL STA. 190+75									10998	3629
CL STA. 4+85 TO CL STA. 8+00		79				79				26
RCL STA. 8+00 TO RCL STA. 31+00			2300					2300		759
LCL STA. 8+00 TO LCL STA. 31+00			2300					2300		759
CL STA. 31+00 TO CL STA. 190+75		3994				3994				1318
RT STA. 4+85 TO RT STA. 190+75	18050				18050					5957
LT STA. 4+85 TO LT STA. 190+75	18144				18144					5988
SIDEROADS	772			95	772			95		0
										445
SUBTOTAL	36966	4073	4600	95	36966	4073	4600	95	10998	18878
TOTAL		45639		95		45639		95	10998	18878

PERMANENT SURVEY MARKERS TO BE ADJUSTED	
LOCATION	EACH
CH 4	
PT 35+49.67 TAB	1
PC 40+07.88 TAB	1
PT 44+45.58 TAB	1
PI 59+57.50 TAB	1
PI 86+37.46 TAB	1
PI 113+05.92	1
PI 164+75.19 TAB	1
TOTAL	7

GUARDRAIL TABULATION					
LOCATION	STEEL PLATE BEAM GUARDRAIL TYPE A	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKERS	GUARDRAIL REMOVAL
	FOOT	EACH	EACH	EACH	FOOT
RT. STA. 70+70 TO RT. STA. 73+95	225	2	2	5	100
LT. STA. 71+50 TO RT. STA. 74+75	225	2	2	5	112.5
TOTAL	450	4	4	10	212.5

PLOT DATE: 5/16/2008 FILE NAME: 46002-shr-schedule.dgn

HAMPTON, LENZINI & RENWICK, INC.
 CIVIL & STRUCTURAL ENGINEERS
 LAND SURVEYORS

3085 STEVENSON DRIVE, SUITE 201
 SPRINGFIELD, ILLINOIS 62703
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 07.0120.320 DATE: 05/06/08
 DESIGNED: L.F.S. CHECKED: DRAWN: W.J.S.

SCHEDULE OF QUANTITIES

F.A.S. 321 / C.H. 4
 SECTION 05-00205-02-RS
 IROQUOIS COUNTY