

CO054


**SUMMARY OF QUANTITIES**

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	28,205	
AR501911	REMOVE AND REPLACE PCC PAVEMENT	S.F.	471.5	
AR605540	CLEAN & SEAL JOINTS	L.F.	3,857	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	4,550	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	4,450	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	2,638	
AR800443	PAVEMENT CLEANING PRIOR TO MARKING	S.F.	3,933	

**INDEX TO SHEETS**

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION PLAN FOR RUNWAY 6/24 STA. 10+00 TO STA. 36+00
5	PROPOSED CONSTRUCTION PLAN FOR RUNWAY 6/24 STA. 36+00 TO STA. 68+00
6	PROPOSED CONSTRUCTION PLAN FOR RUNWAY 11/29 STA. 100+00 TO STA. 126+00
7	PROPOSED CONSTRUCTION PLAN FOR RUNWAY 11/29 STA. 126+00 TO STA. 152+00
8	PROPOSED CONSTRUCTION PLAN FOR RUNWAY 11/29 STA. 152+00 TO STA. 165+00
9	PROPOSED ENHANCED PAVEMENT MARKING DETAILS
10	PROPOSED ENHANCED PAVEMENT MARKING DETAILS
11	PROPOSED ENHANCED PAVEMENT MARKING DETAILS

DATE	REVISION	BY



COLES COUNTY AIRPORT AUTHORITY  
 A.I.P. PROJ.: 3-17-0066-B21  
 IL PROJ.: MTO-3813

H&E Project No. 08A0008D_0800 Filename R-002FLP.DWG Scale N/A Date 04/15/08	LAYOUT DPE 04/15/08 DRAWN DPE 04/15/08 REVIEWED CAH 05/01/08
--	--



**PAVEMENT REPAIRS & ENHANCED MARKING**  
**SUMMARY OF QUANTITIES AND INDEX TO SHEETS**