SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN)	CONSTRUCTION TYPE CODE 0005 100% STATE					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10	10					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	317	317					
25200110	SODDING, SALT TOLERANT	SQ YD	317	317					
25200200	SUPPLEMENTAL WATERING	UNIT	3.2	3.2					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	17					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	623	623					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	242	242					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	218	218					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1269	1269					
42001300	PROTECTIVE COAT	SQ YD	786	786					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	25	25					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN)	CONSTRUCTION TYPE CODE 0005 100% STATE					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2889	2889					
42400800	DETECTABLE WARNINGS	SQ FT	546	546					
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	11326	11326					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	25	25					
44000600	SIDEWALK REMOVAL	SQ FT	3177	3177					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1293	1293					
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	233	233					
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	405	405					
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	486	486					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	5					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1					
60260100	INLETS TO BE ADJUSTED	EACH	2	2					
60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pwidot\obrauch\d0246778\D1093-sht-plan.dgn	USER NAME = obrauch	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1000.000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/20/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

RANDOLPH ST. FROM LATHROP AVE. TO IL 43 (HARLEM AVE.)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1411	2010-103-RS	COOK	14	3
		CONTRACT NO. 60M26		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT