## SUMMARY OF QUANTITIES

| CODE NO. | ITEM DESCRIPTION | UNIT | URBAN TOTAL QUANTITY | 100% STATE CONSTRUCTION TYPE CODE 0005 QUANTITY | |
|---|---|---|---|---|---|
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 88 | 88 | |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 88 | 88 | |
| 25200200 | SUPPLEMENTAL WATERING | UNIT | 6 | 6 | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 250 | 250 | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 1,407 | 1,407 | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 412 | 412 | |
| 40600827 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 9,639 | 9,639 | |
| 40603595 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 | TON | 22,889 | 22,889 | |
| 42001300 | PROTECTIVE COAT | SQ YD | 121 | 121 | |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SQ YD | 227,459 | 227,459 | |
| 44002214 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2" | SQ YD | 2,046 | 2,046 | |
| 44201765 | CLASS D PATCHES, TYPE II, 10 INCH | SQ YD | 475 | 475 | |
| 44201769 | CLASS D PATCHES, TYPE III, 10 INCH | SQ YD | 130 | 130 | |
| 44201771 | CLASS D PATCHES, TYPE IV, 10 INCH | SQ YD | 1,100 | 1,100 | |

* INDICATES SPECIALTY ITEM

## SUMMARY OF QUANTITIES

| CODE NO. | ITEM DESCRIPTION | UNIT | URBAN TOTAL QUANTITY | 100% STATE CONSTRUCTION TYPE CODE 0005 QUANTITY | |
|---|---|---|---|---|---|
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 7,710 | 7,710 | |
| 60250200 | CATCH BASINS TO BE ADJUSTED | EACH | 7 | 7 | |
| 60251500 | CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE | EACH | 1 | 1 | |
| 60403800 | LIDS, TYPE 1, CLOSED LID | EACH | 2 | 2 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 7 | 7 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | |
| 70100600 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701336 | L SUM | 1 | 1 | |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 | |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 87,816 | 87,816 | |
| 70300210 | TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS | SQ FT | 5,520 | 5,520 | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 312,046 | 312,046 | |

* INDICATES SPECIALTY ITEM

Rev.

COPYRIGHT © 2014, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-001007 EXPIRES 4/30/2015
263mcc 5/22/2014 3:27:43 PM
...\plotdrv\pdf-BW_Default.pltcfg
...\100153_W0-17-500.tbl
...\Crystal Lake\IDOT\100153_W0-17-&38 Rt 47 to Rt 31\CADD-SURVEY\DRAWINGS\DGNS\100153-W0-17-500.sht

| | | | |
|---|---|---|---|
| BAXTER & WOODMAN Consulting Engineers | DESIGNED - TLH | REVISED - 7-20-11 IDOT REVIEW | |
| | DRAWN - UKB | REVISED - 10-22-12 IDOT REVIEW | |
| | CHECKED - RWL | REVISED - 5-12-14 UPDATE | |
| | DATE - 12-17-10 | FILE - 100153-W0-17-500.sht | |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 38**
**IL ROUTE 47 TO IL ROUTE 31**
**SUMMARY OF QUANTITIES**

SCALE: STA. TO STA.

| F.A.P RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 347 | 4R-RS-8 | KANE | 65 | 3 |
| C-91-308-11 | | CONTRACT NO. 60N38 | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED AID PROJECT | | |