

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				URBAN ROADWAY 100% STATE 0005
20200100	EARTH EXCAVATION	CU YD	35	35
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	296	296
25200110	SODDING, SALT TOLERANT	SQ YD	296	296
25200200	SUPPLEMENTAL WATERING	UNIT	15	15
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	30
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5177	5177
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1729	1729
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10542	10542
42001300	PROTECTIVE COAT	SQ YD	328	328
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1797	1797
42400800	DETECTABLE WARNINGS	SQ FT	308	308
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	123720	123720
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1370	1370
44000600	SIDEWALK REMOVAL	SQ FT	1797	1797

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				URBAN ROADWAY 100% STATE 0005
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	50	50
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	640	640
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	520	520
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	150	150
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	525	525
50300300	PROTECTIVE COAT	SQ YD	294	294
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	7	7
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10
60404950	FRAMES AND GRATES, TYPE 24	EACH	7	7
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1370	1370
* 06900200	NON-SPECIAL WASTE DISPOSAL	CU YD	35	35
60600605	CONCRETE CURB, TYPE B	FOOT	405	405
* 06900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
* 06900530	SOIL DISPOSAL ANALYSIS	EACH	1	1
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1