

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0004 80% FEDERAL 20% STATE ROADWAY	0021 80% FEDERAL 20% STATE TRAFFIC SIGNALS	0021 80% FEDERAL 20% STATE INTERCONNECT	0021 100% VILLAGE OF PINGREE GROVE FIRE PROT. DIST. SAFETY (EVP)	0021 80% FEDERAL 20% STATE LIGHTING	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	170	170					
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	345	345					
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	2,447	2,447					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	6,184	6,184					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2	2					
50105220	PIPE CULVERT REMOVAL	FOOT	28	28					
50200100	STRUCTURE EXCAVATION	CU YD	166	166					
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	72	72					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1290	1290					
50300225	CONCRETE STRUCTURES	CU YD	9.9	9.9					
50800515	BAR SPLICERS	EACH	148	148					
50300300	PROTECTIVE COAT	SQ YD	4	4					
51500100	NAME PLATES	EACH	1	1					
54003000	CONCRETE BOX CULVERTS	CU YD	118	118					
54010302	PRECAST CONCRETE BOX CULVERTS 3' X 2'	FOOT	20	20					
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	80	80					
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	70	70					

FILE NAME = WFILEL

SHT. PLAN

USER NAME = *USER*	DESIGNED - MTM	REVISED -
DRAWN - MTM	CHECKED - BA	REVISED -
PLOT SCALE = *SCALE*	DATE - 3/31/14	REVISED -
PLOT DATE = *DATE*		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET 4 OF 13 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	106-S-N-2	KANE	147	7
CONTRACT NO. 60T09			ILLINOIS FED. AID PROJECT	

Rev.