

FILE NAME: C:\projects\110115\110115.dwg User: User Date: 11/15/11 10:28:15 AM
 Item 7 - Various Services\Work Order No. 11 104811 - 15 28 at 11:47:48 AM
 11/15/11 10:28:15 AM
 SMT_Plan

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				0004 80% FEDERAL 20% STATE	0021 80% FEDERAL 20% STATE	0021 80% FEDERAL 20% STATE	0021 100% VILLAGE OF PINGREE GROVE	0021 80% FEDERAL 20% STATE
				ROADWAY	TRAFFIC SIGNALS	INTERCONNECT	FIRE PROT. DIST. SAFETY (EVP)	LIGHTING
△ 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	183		58			125
△ 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	103		103			
△ 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,356		516			840
△ 81400200	HEAVY-DUTY HANDHOLE	EACH	12		11	1		
△ 81400300	DOUBLE HANDHOLE	EACH	2		2			
△ 81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	6,035					6,035
△ 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	140					140
△ 81702160	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 1/0	FOOT	420					420
△ 81800300	AERIAL CABLE 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	1,270					1,270
△ 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	30					30
△ 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	6					6
△ 82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480 VOLT, 100AMP	EACH	1					1
△ 83050805	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 12 FT. DAVIT ARM	EACH	26					26
△ 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	338					338

△ SPECIALTY ITEM

Rev.

USER NAME: c:\projects\110115\110115.dwg	DESIGNED - MTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 345	SECTION 106-S-N-2	COURTY KANE	TOTAL SHEETS 147	SHEET NO. 11
PLOT SCALE = 1/8" = 1'-0"	CHECKED - BA	REVISED -		SCALE: N.T.S.	SHEET 8	OF 13 SHEETS	STA. TO STA.	CONTRACT NO. 60T09		ILLINOIS FED. AID PROJECT	
PLOT DATE = 4/1/2014	DATE - 3/31/14	REVISED -									