

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 80% FED 20% STATE ROADWAY	0021 80% FED 15% STATE 2.5% HOFFMAN ESTATES 2.5% STREAM- WOOD T. SIGNALS	0021 100% HOFFMAN ESTATES E.V.P.			
*81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	28		28				
*81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	125		125				
*81400100	HANDHOLE	EACH	3		3				
*81400200	HEAVY-DUTY HANDHOLE	EACH	2		2				
*85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2				
*87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2825		2825				
*87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	425		425				
*87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	420		420				
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1145		1145				
*87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1350		1350				
*87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT. *SPECIALTY ITEMS	EACH	1		1				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 80% FED 20% STATE ROADWAY	0021 80% FED 15% STATE 2.5% HOFFMAN ESTATES 2.5% STREAM- WOOD T. SIGNALS	0021 100% HOFFMAN ESTATES E.V.P.			
*87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1		1				
*87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4		4				
*87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	11		11				
*87900200	DRILL EXISTING HANDHOLE	EACH	9		9				
*88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4		4				
*88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4		4				
*88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4		4				
*88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		4				
*88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2				
*88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8		8				
*88500100	INDUCTIVE LOOP DETECTOR	EACH	1		1				
*88600100	DETECTOR LOOP, TYPE I	FOOT	515		515				

FILE NAME :	USER NAME : gggf10001	DESIGNED -	REVISED -
c:\pwworking\ggg10001\082483-111\0109-211-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
BARRINGTON ROAD AT BODE ROAD			
SCALE: NONE	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.P. RTE. 362	SECTION 010SR-M121	COUNTY COOK	TOTAL SHEETS 48	SHEET NO. 5
CONTRACT NO. 60T96				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				