



- 1 PROP. THERMOPLASTIC PVT. MARKING 4", LINE, WHITE (TYP.)
- 2 PROP. THERMOPLASTIC PVT. MARKING 4", DOUBLE YELLOW (TYP.)
- 3 PROP. THERMOPLASTIC PVT. MARKING 4", SKIP DASH, YELLOW (TYP.)
- 4 PROP. THERMOPLASTIC PVT. MARKING 4", LINE, YELLOW (TYP.)
- 5 PROP. THERMOPLASTIC PVT. MARKING 6", LINE, WHITE (TYP.)
- 6 PROP. THERMOPLASTIC PVT. MARKING 6", SKIP DASH, WHITE (TYP.)
- 7 PROP. THERMOPLASTIC PVT. MARKING 12", BAR, WHITE (TYP.)
- 8 PROP. THERMOPLASTIC PVT. MARKING 12", DIAGONALS, WHITE (TYP.)
- 9 PROP. THERMOPLASTIC PVT. MARKING 12", DIAGONALS, YELLOW (TYP.)
- 10 PROP. THERMOPLASTIC PVT. MARKING 24", STOP BAR, WHITE (TYP.)
- 11 PROP. THERMOPLASTIC PVT. MARKING LETTERS & SYMBOLS, WHITE (TYP.)
- 12 PROP. SIDEWALK RAMP REPAIR

PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"

PROPOSED POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50, 3/4"

PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1 1/2"

FILE NAME =	USER NAME = osbornnp	DESIGNED -	REVISED -
es:\pwork\pwork\osbornnp\0313225\01912-sht-plan.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/22/2014	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROADWAY AND PAVEMENT  
MARKING PLAN

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	(21x.29V&132)RS-2	MCHENRY	34	12
CONTRACT NO. 60V12				
ILLINOIS FED. AID PROJECT				