

PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"
 PROPOSED POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50, 3/4"
 PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70", 1 1/2"

MATCH LINE STA. 299+00

MATCH LINE STA. 314+00

IL. ROUTE 173

SHOULDER RUMBLE STRIPS, 8"

1 300+00 1 305+00 1 310+00

NOLAN ST.

- 1 PROP. THERMOPLASTIC PVMT. MARKING 4", LINE, WHITE (TYP.)
- 2 PROP. THERMOPLASTIC PVMT. MARKING 4", DOUBLE YELLOW (TYP.)
- 3 PROP. THERMOPLASTIC PVMT. MARKING 4", SKIP DASH, YELLOW (TYP.)
- 4 PROP. THERMOPLASTIC PVMT. MARKING 4", LINE, YELLOW (TYP.)
- 5 PROP. THERMOPLASTIC PVMT. MARKING 6", LINE, WHITE (TYP.)
- 6 PROP. THERMOPLASTIC PVMT. MARKING 6", SKIP DASH, WHITE (TYP.)
- 7 PROP. THERMOPLASTIC PVMT. MARKING 12", BAR, WHITE (TYP.)
- 8 PROP. THERMOPLASTIC PVMT. MARKING 12", DIAGONALS, WHITE (TYP.)
- 9 PROP. THERMOPLASTIC PVMT. MARKING 12", DIAGONALS, YELLOW (TYP.)
- 10 PROP. THERMOPLASTIC PVMT. MARKING 24", STOP BAR, WHITE (TYP.)
- 11 PROP. THERMOPLASTIC PVMT. MARKING LETTERS & SYMBOLS, WHITE (TYP.)
- 12 PROP. SIDEWALK RAMP REPAIR

IL. ROUTE 173

OAK GROVE RD.

MATCH LINE STA. 314+00

MATCH LINE STA. 329+00

1 315+00 1 320+00 1 325+00

OMISSION BEGINS STA. 318+09.5

PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"
 PROPOSED POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50, 3/4"
 PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70", 1 1/2"

FILE NAME =	USER NAME = osbornnp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ROADWAY AND PAVEMENT MARKING PLAN				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	Default	DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	MCHENRY	34	18
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -								CONTRACT NO. 60V12		
	PLOT DATE = 5/22/2014	DATE -	REVISED -								ILLINOIS FED. AID PROJECT		