PROPOSED SIGN SCHEDULE

SIGN I.D.	ROAD	PROP STA	PROP OFFSET	SIGN DESCRIPTION	GROUND MOUNTING TYPE	TYPE/I.D.	DIMENSIONS HEIGHT	DIMENSIONS WIDTH	AREA SF	72000105 SIGN PANEL TYPE 1	72800100 TELESCOPING STEEL SIGN SUPPORT	73000100 WOOD SIGN SUPPORT	X7280105 TELESCOPING STEEL SIGN SUPPORT (SPECIAL)
							FT	FT	SF	SF	FT	FT	FT
S-279	US ROUTE 14	387+00	67' L	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	15.0		
S-280	US ROUTE 14	375+75	50' L	SIGNAL AHEAD	TELESCOPING	W3-3	2.50	2.50	6.25	6.25	17.5		
S-280A				LAKE SHORE DRIVE		CUSTOM	0.67	3.00	2.01	2.01			
S-281	US ROUTE 14	366+64	72' L	RIGHT TURN ONLY	TELESCOPING	R3-5R	3.00	2.50	7.50	7.50	17.0		
S-283	LAKE SHORE DRIVE	45+91	45' L	US ROUTE 14	TELESCOPING	M1-4	2.50	2.00	5.00	5.00	17.0		
S-283A				TWO DIRECTIONAL ARROW		M6-4	1.25	1.75	2.19	2.19			
S-284	US ROUTE 14	363+00	53' L	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	16.5		
S-286	US ROUTE 14	350+75	11' L	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	14.0		
S-286A				U TURN ONLY		CUSTOM	3.00	2.50	7.50	7.50			
S-287	US ROUTE 14	348+65	11' L	U TURN ONLY	TELESCOPING	CUSTOM	3.00	2.50	7.50	7.50	14.0		
S-288	US ROUTE 14	343+30	53' L	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	18.0		
S-289	US ROUTE 14	338+80	54' L	SIGNAL AHEAD	TELESCOPING	W3-3	2.50	2.50	6.25	6.25	18.0		
S-289A				WEST LAKE SHORE DRIVE		CUSTOM	0.67	4.00	2.68	2.68			
S-290	US ROUTE 14	325+85	11' R	LEFT TURN ONLY	TELESCOPING	R3-5L	2.50	2.00	5.00	5.00	13.5		
S-290A				KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00			
S-291	US ROUTE 14	326+10	83' L	RIGHT TURN ONLY	TELESCOPING	R3-5R	3.00	2.50	7.50	7.50	17.0		
S-295	RIDGEFIELD ROAD	850+48	67' R	US ROUTE 14	TELESCOPING	CUSTOM	1.00	4.00	4.00	4.00	15.0		
S-295A				US ROUTE 14		CUSTOM	1.00	4.00	4.00	4.00			
S-295B				RIDGEFIELD ROAD		CUSTOM	1.33	4.50	6.00	6.00			
S-295C				RIDGEFIELD ROAD		CUSTOM	1.33	4.50	6.00	6.00			
S-296	LILY POND ROAD	800+75	46' R	US ROUTE 14	TELESCOPING	CUSTOM	1.00	4.00	4.00	4.00	15.0		
S-296A				US ROUTE 14		CUSTOM	1.00	4.00	4.00	4.00			
S-296B				LILY POND ROAD		CUSTOM	1.33	4.50	6.00	6.00			
S-296C				LILY POND ROAD		CUSTOM	1.33	4.50	6.00	6.00			
S-297	RIDGEFIELD ROAD	854+65	29' L	CURVE LEFT/ADVISORY SPEED	TELESCOPING	W1-2a L	3.00	3.00	9.00	9.00			17.0
S-298	LILY POND ROAD	807+00	29' L	CURVE RIGHT/ADVISORY SPEED	TELESCOPING	W1-2a R	3.00	3.00	9.00	9.00	16.0		
S-299	US ROUTE 14	325+40	10' L	DO NOT ENTER	TELESCOPING	R5-1	3.00	3.00	9.00	9.00	14.0		
S-299A				STOP HERE ON RED		R10-6A	2.50	2.00	5.00	5.00			
S-300	US ROUTE 14	329+70	82' L	RIGHT TURN ONLY	TELESCOPING	R3-5R	3.00	2.50	7.50	7.50	17.0		
S-301	US ROUTE 14	167+36	15' R	LEFT TURN ONLY	TELESCOPING	R3-5L	2.50	2.00	5.00	5.00	13.5		
S-302	RIDGEFIELD ROAD	854+40	27' R	EAST	TELESCOPING	M3-2	1.00	2.00	2.00	2.00			16.5
				MCHENRY COUNTY V25		M1-6	2.00	2.00	4.00	4.00			
				RIDGEFIELD RD		W17-I100	0.75	3.00	2.25	2.25			
S-303	RIDGEFIELD ROAD	854+38	29' L	END	TELESCOPING	M4-6	1.00	2.00	2.00	2.00			16.0
				MCHENRY COUNTY V25		M1-6	2.00	2.00	4.00	4.00			
				RIDGEFIELD RD		W17-I100	0.75	3.00	2.25	2.25			
S-304	US ROUTE 14	476+00	56' L	JUNCTION	TELESCOPING	M2-1	1.25	1.75	2.19	2.19			17.0
				MCHENRY COUNTY V25		M1-6	2.00	2.00	4.00	4.00			
				RIDGEFIELD RD		W17-I100	0.75	3.00	2.25	2.25			
				ADVANCE TURN ARROW		M5-1R	1.75	1.25	2.19	2.19			
S-305	US ROUTE 14	468+24	52' L	MCHENRY COUNTY V25	TELESCOPING	M1-6	2.00	2.00	4.00	4.00			15.5
				RIDGEFIELD RD		W17-I100	0.75	3.00	2.25	2.25			
				RIGHT DIRECTIONAL ARROW		M6-1R	1.75	1.25	2.19	2.19			

..\SGN00.14.DGN..\TB009#JJ.DGN..\SGN00.14.DGN
11-07-2013,16:32:24 HECHTBR I:\DOCUMENT\193439B1\CIVIL\DGN\SGN00.J-.DGN