SUMMARY OF QUANTITIES

URBAN

	PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY		SHARED-USE PATH	LIGHTING	TRAFFIC SIGNALS							WATER MAIN AND SANITARY SEWER	
									US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ ILLUMINATED STREET NAME SIGNS	INTERCONNECT		
					100% STATE	MCHENRY COUNTY COLLEGE 100%	80% STATE 20% MCCD	100% STATE	MCHENRY COUNTY COLLEGE 100%	93.3% STATE 6.7% MCHENRY COUNTY	100% STATE	90% STATE 5% Crystal Lk 5% McHenry Co?	90% STATE 10% CRYSTAL LAKE	100% CRYSTAL LAKE	100% STATE	100% STATE	100% CRYSTAL LAKE
					0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,763	1,727	36											
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,763	1,727	36											
*	25100115	MULCH, METHOD 2	ACRE	8.90	8.90												
*	25100630	EROSION CONTROL BLANKET	SQ YD	85,813	85,813												
*	25200110	SODDING, SALT TOLERANT	SQ YD	8,555	8,555												
	28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	191	191												
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,660	2,660												
	28000305	TEMPORARY DITCH CHECKS	FOOT	1,848	1,848												
	28000400	PERIMETER EROSION BARRIER	FOOT	14,018	14,018												
	28000500	INLET AND PIPE PROTECTION	EACH	22	22												
	28000510	INLET FILTERS	EACH	238	238												
	28001000	AGGREGATE (EROSION CONTROL)	TON	7	7												
	28100105	STONE RIPRAP, CLASS A3	SQ YD	131	131												
	28200200	FILTER FABRIC	SQ YD	131	131												
*	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	117,174	115,140	2,034											

* SPECIALTY ITEM

FILE NAME = S:\1606\CADD Sheets\0162517-sht-500.dgn	USER NAME = .USERNAME.	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/17/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. 5 OF 431 SHEETS | STA. | TO STA.

Rev. 7-18-14

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-3	MCHENRY	431	5
		CONTRACT NO. 62517		
	ILLINOIS FED. AID PROJECT			