

## SUMMARY OF QUANTITIES

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN		SHARED-USE PATH	LIGHTING	TRAFFIC SIGNALS						WATER MAIN AND SANITARY SEWER				
				ROADWAY				100% STATE	100% STATE	US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ILLUMINATED STREET NAME SIGNS	INTERCONNECT	100% STATE	100% CRYSTAL LAKE
				100% STATE	MCHENRY COUNTY COLLEGE 100%													
0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043			
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SD YD	4,330	2,895	1,435													
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SD YD	84,159	83,770	389													
42001300	PROTECTIVE COAT	SD YD	113,466	112,993	473													
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SD YD	1,275	1,275														
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SD FT	21,025	21,025														
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SD FT	764	764														
42400800	DETECTABLE WARNINGS	SD FT	412	278		134												
44000100	PAVEMENT REMOVAL	SD YD	87,861	86,501	1,360													
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SD YD	2,044	1,512	532													
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SD YD	11,350	11,350														
44000200	DRIVEWAY PAVEMENT REMOVAL	SD YD	5,658	5,567	91													
44000300	CURB REMOVAL	FOOT	1,940	1,790	150													
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	11,773	11,773														
44000600	SIDEWALK REMOVAL	SD FT	17,304	17,304														
44003100	MEDIAN REMOVAL	SD FT	2,032	2,032														

Rev. 7-18-14

\* SPECIALTY ITEM

FILE NAME : S:\1606\CADD Sheets\0162517-sh-500.dgn	USER NAME : USERNAME	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE    SHEET NO. 7 OF 431 SHEETS    STA.    TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-3	MCHENRY	431	7
CONTRACT NO. 62517			ILLINOIS FED. AID PROJECT	