

SUMMARY OF QUANTITIES

URBAN

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY		SHARED-USE PATH	LIGHTING	TRAFFIC SIGNALS								WATER MAIN AND SANITARY SEWER	
				100% STATE	MCHENRY COUNTY COLLEGE 100%	80% STATE 20% MCCC	100% STATE	US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ILLUMINATED STREET NAME SIGNS	INTERCONNECT	100% STATE	100% CRYSTAL LAKE	
				0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	91,266	90,799	467												
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	266	266													
35102200	AGGREGATE BASE COURSE, TYPE B 10"	SQ YD	2,833			2,833											
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	683	683													
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1,443	1,443													
35600713	HOT-MIX ASPHALT BASE COURSE WIDENING, 9 1/4"	SQ YD	4,946	4,946													
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4													
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	794	771	23												
40600895	CONSTRUCTING TEST STRIP	EACH	1	1													
40600990	TEMPORARY RAMP	SQ YD	373	373													
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	269			269											
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	623	623													
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	442	281		161											
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	208	163	45												
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1,539	1,539													

15 * SPECIALTY ITEM

Rev.

FILE NAME : S:\1606\CADD Sheets\0162517-sht-500.dgn	USER NAME : USERNAME	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A. RTE. 305	SECTION 27R-3	COUNTY MCHENRY	TOTAL SHEETS 431	SHEET NO. 6	
PLOT SCALE : 100.0000' / 1"	CHECKED -	REVISED -	REVISED -		SCALE: NONE	SHEET NO. 6 OF 431 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 62517				
PLOT DATE : 6/17/2014	DATE -	REVISED -	REVISED -									