

SUMMARY OF QUANTITIES

URBAN

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY		SHARED-USE PATH	LIGHTING	TRAFFIC SIGNALS							WATER MAIN AND SANITARY SEWER		
				100% STATE	MCHENRY COUNTY COLLEGE 100%			80% STATE 20% MCCO	100% STATE	US 14 & LUCAS ROAD	US 14 & RIDGFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ILLUMINATED STREET NAME SIGNS	INTERCONNECT	100% STATE
				0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043
44004250	PAVED SHOULDER REMOVAL	SO YD	407	407													
44200071	PAVEMENT PATCHING, TYPE IV, 6 INCH	SO YD	27	27													
44200112	PAVEMENT PATCHING, TYPE III, 9 INCH	SO YD	55	55													
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SO YD	19	19													
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SO YD	59	59													
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SO YD	29	29													
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SO YD	435	435													
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH	SO YD	121	121													
44200196	PAVEMENT PATCHING, TYPE III, 16 INCH	SO YD	128	128													
44200198	PAVEMENT PATCHING, TYPE IV, 16 INCH	SO YD	573	573													
44200204	PAVEMENT PATCHING, TYPE III, 17 INCH	SO YD	64	64													
44200206	PAVEMENT PATCHING, TYPE IV, 17 INCH	SO YD	99	99													
44213200	SAW CUTS	FOOT	7,230	7,084	146												
48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SO YD	223	223													
48300415	PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	SO YD	1,021	1,021													

* SPECIALTY ITEM

FILE NAME : S:\1606\CADD Sheets\0162517-akt-500.dgn	USER NAME : .USERNAME.	DESIGNED -	REVISOR -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A. RTE. 305	SECTION 27R-3	COUNTY MCHENRY	TOTAL SHEETS 431	SHEET NO. 8
		DRAWN -	REVISOR -		SCALE: NONE	SHEET NO. 8 OF 431 SHEETS	STA. TO STA.	CONTRACT NO. 62517				
		CHECKED -	REVISOR -		ILLINOIS FED. AID PROJECT							
		DATE -	REVISOR -									