

**URBAN**  
**SUMMARY OF QUANTITIES**

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS													WATER MAIN AND SANITARY SEWER	
				ROADWAY		SHARED-USE PATH	LIGHTING	US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ILLUMINATED STREET NAME SIGNS	INTERCONNECT	100% STATE	100% CRYSTAL LAKE		
				100% STATE	MCHENRY COUNTY COLLEGE 100%	80% STATE 20% MCHENRY COUNTY	100% STATE	MCHENRY COUNTY COLLEGE 100%	93.3% STATE 6.7% MCHENRY COUNTY	100% STATE	90% STATE 10% CRYSTAL LAKE	90% STATE 10% CRYSTAL LAKE	100% CRYSTAL LAKE	100% STATE	100% STATE	100% CRYSTAL LAKE		
				0003	0003	0028		0021	0021	0021	0021	0021	0021	0021	0021	0043	0043	
* A2006720	TREE, QUERCUS MACROCARPA (BUR OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	27	27														
* A2007210	TREE, QUERCUS X MACDANIELLI CLEMONS (HERITAGE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	12	12														
* A2016818	TREE, QUERCUS SCHUETTI (SWAMP BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	6	6														
* B2001616	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	16	16														
* B2006220	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	53	53														
* C2012024	SHRUB, VIBURNUM DENTATUM SYNNESTVEDT (CHICAGO LUSTRE ARROWWOOD VIBURNUM), 2' HEIGHT, BALLED AND BURLAPPED	EACH	116	116														
* K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	12.52	12.52														
* K0013030	PERENNIAL PLANTS, WETLAND TYPE, 2" DIAMETER BY 4" DEEP PLUG	UNIT	6.08	6.08														
X0322464	ABANDON AND FILL EXISTING SANITARY MANHOLE	EACH	1														1	
X0323260	SEDIMENT BASIN	EACH	1	1														
X0323449	REMOVE EXISTING WATER VALVE	EACH	9														9	
X0324078	CONFLICT MANHOLES	EACH	1														1	
X0325003	REMOVE EXISTING VALVE AND VAULT	EACH	5														5	
* X0325860	TEMPORARY WOOD POLE, 60 FT., CLASS 4, WITH 15 FT. MAST ARM, INSTALL ONLY	EACH	19						19									
* X0326656	RELOCATE EXISTING TRAFFIC SIGNAL CONTROLLER AND CABINET, COMPLETE	EACH	1									1						

\* SPECIALTY ITEM

FILE NAME : S:\1606\CA00 Sheets\0162517-sh1-500.dgn	USER NAME : .\USERNAME.	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A. RTE. 305	SECTION 27R-3	COUNTY MCHENRY	TOTAL SHEETS 431	SHEET NO. 11M
		DRAWN -	REVISED -		SCALE: NONE	SHEET NO. 11M OF 431 SHEETS	STA.	TO STA.	CONTRACT NO. 62517			
		CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE -	REVISED -									