

**SUMMARY OF QUANTITIES**

**URBAN**

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY		SHARED-USE PATH	LIGHTING	TRAFFIC SIGNALS								WATER MAIN AND SANITARY SEWER		
				100% STATE	MCHENRY COUNTY COLLEGE 100%			80% STATE 20% MCCO	100% STATE	US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ILLUMINATED STREET NAME SIGNS	INTERCONNECT	100% STATE	100% CRYSTAL LAKE
				0003	0003			0028	0021	0021	0021	0021	0021	0021	0021	0021	0021	0043
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	44,791	44,771	20													
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	29,727	29,727														
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	796	796														
61101020	STORM SEWERS PROTECTED, CLASS A, 18"	FOOT	496	496														
61133300	FIELD TILE JUNCTION VAULTS, 4' DIA.	EACH	7	7														
61140600	STORM SEWERS (SPECIAL), 18"	FOOT	550	550														
63200310	GUARDRAIL REMOVAL	FOOT	48	48														
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1,240	1,240														
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1														
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3														
67100100	MOBILIZATION	L SUM	1	1														
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	730	730														
70106800	CHANGEABLE MESSAGE SIGN	CAL MC	48	48														
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,310	2,310														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	41,088	41,088														

\* SPECIALTY ITEM