SUMMARY OF QUANTITIES

URBAN

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY		SHARED-USE PATH	LIGHTING	TRAFFIC SIGNALS							WATER MAIN AND SANITARY SEWER	
								US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ ILLUMINATED STREET NAME SIGNS	INTERCONNECT		
				100% STATE	MCHENRY COUNTY COLLEGE 100%	80% STATE 20% MCCO	100% STATE	MCHENRY COUNTY COLLEGE 100%	93.3% STATE 6.7% MCHENRY COUNTY	100% STATE	90% STATE 10% CRYSTAL LAKE	90% STATE 10% CRYSTAL LAKE	100% CRYSTAL LAKE	100% STATE	100% STATE	100% CRYSTAL LAKE
				0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043
* 81400100	HANDHOLE	EACH	39					5	4	7	4	4		15		
* 81400200	HEAVY-DUTY HANDHOLE	EACH	16					4	3	4	2	3				
* 81400300	DOUBLE HANDHOLE	EACH	9					2	1	2	2	2				
* 81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	4,500				4,500									
* 81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	80				80									
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	4,700				4,700									
* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	22				22									
* 82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	1				1									
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	18				18									
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	180				180									
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	18				18									
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	19				19									
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	16				16									
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	16				16									
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	5					1	1	1	1	1				

* SPECIALTY ITEM

FILE NAME = S:\1606\CADD Sheets\0162517-sht-500.dgn	USER NAME = .USERNAME.	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 6/17/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. 11H OF 431 SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-3	MCHENRY	431	11H
		CONTRACT NO. 62517		
	ILLINOIS FED. AID PROJECT			