SUMMARY OF QUANTITIES

URBAN

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY		SHARED-USE PATH	LIGHTING	TRAFFIC SIGNALS							WATER MAIN AND SANITARY SEWER	
								US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ ILLUMINATED STREET NAME SIGNS	INTERCONNECT		
				100% STATE	MCHENRY COUNTY COLLEGE 100%	80% STATE 20% MCCD	100% STATE	MCHENRY COUNTY COLLEGE 100%	93.3% STATE 6.7% MCHENRY COUNTY	100% STATE	90% STATE 10% CRYSTAL LAKE	90% STATE 10% CRYSTAL LAKE	100% CRYSTAL LAKE	100% STATE	100% STATE	100% CRYSTAL LAKE
				0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043
* 87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	12,473											12,473		
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	12,473											12,473		
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2,719					195			1,356	1,168				
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	7,571					628			1,412	1,218	4,313			
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	10,334					1331	2,718	2,609	1,852	1,824				
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	5,622					1536	249	2,318	816	703				
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	12,513					2817	1,295	4,963	1,353	2,085				
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	380					72	134	39	44	91				
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	3,474					630	746	924	573	601				
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	6						2	2	1	1				
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	10					3	1	2	2	2				
* 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1						1							
* 87601100	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE I	EACH	2								1	1				
* 87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	2								2					
* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2									2				

* SPECIALTY ITEM

FILE NAME = S:\1606\CADD Sheets\0162517-sht-SOD.dgn	USER NAME = .USERNAME.	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE. 305	SECTION 27R-3	COUNTY MCHENRY	TOTAL SHEETS 431 / SHEET NO. 111
		DRAWN -	REVISED -					CONTRACT NO. 62517	
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -		SCALE: NONE / SHEET NO. 111 OF 431 SHEETS / STA. / TO STA.			ILLINOIS FED. AID PROJECT	
	PLOT DATE = 6/17/2014	DATE -	REVISED -						