

SUMMARY OF QUANTITIES

URBAN

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS													WATER MAIN AND SANITARY SEWER	
				ROADWAY		SHARED-USE PATH	LIGHTING	US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ILLUMINATED STREET NAME SIGNS	INTERCONNECT	100% STATE	100% CRYSTAL LAKE		
				100% STATE	MCHENRY COUNTY COLLEGE 100%	80% STATE 20% MCCO	100% STATE	MCHENRY COUNTY COLLEGE 100%	93.3% STATE 6.7% MCHENRY COUNTY	100% STATE	90% STATE 10% CRYSTAL LAKE	90% STATE 10% CRYSTAL LAKE	100% CRYSTAL LAKE	100% STATE	100% STATE	100% CRYSTAL LAKE		
				0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043		
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	546	546														
550A4000	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	396	396														
550A4100	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	127	127														
550A4500	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	353	353														
550A4800	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 18"	FOOT	1,116	1,116														
550A4900	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 24"	FOOT	1,639	1,639														
550A5000	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 27"	FOOT	33	33														
550A5100	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 30"	FOOT	719	719														
55100400	STORM SEWER REMOVAL 10"	FOOT	254	254														
55100500	STORM SEWER REMOVAL 12"	FOOT	1,030	1,030														
55100700	STORM SEWER REMOVAL 15"	FOOT	499	499														
55100900	STORM SEWER REMOVAL 18"	FOOT	506	506														
56100005	DUCTILE IRON WATER MAIN TEE, 6" X 6"	EACH	1														1	
56100015	DUCTILE IRON WATER MAIN TEE, 8" X 6"	EACH	1														1	
56100050	DUCTILE IRON WATER MAIN TEE, 12" X 6"	EACH	11														11	

* SPECIALTY ITEM

FILE NAME : S:\1606\CADD Sheets\0162517-shc-500.dgn	USER NAME : USERNAME	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			305	2TR-3	MCHENRY	431	11	
		CHECKED -	REVISED -			CONTRACT NO. 62517					
		DATE -	REVISED -			ILLINOIS/FED. AID PROJECT					

SCALE: NONE SHEET NO. 11 OF 431 SHEETS STA. TO STA.