

DRIVEWAY SCHEDULE																
STATION	20200100 EARTH EXCAVATION AGGREGATE DRIVEWAY (CU YD)	40600827 PLB MM IL- 4.75 N50 (TON)	40603340 HMA SC "D" N70 (TON)	44000158 HMA SURF REM 2 1/4 (SQ YD)	44000200 DRIVEWAY PAVEMENT REMOVAL (SQ YD)	44000300 CURB REMOVAL (FT)	44000500 COMB CURB & GUTTER REMOVAL (FT)	60600605 CONCRETE CURB, TYPE B (FT)	60603800 COMB CONCRETE CURB & GUTTER, TYPE B-6.12 (FT)	60605000 COMB CC&G TB6.24 (FOOT)	40603335 HMA SURFACE COURSE, MIX "D", N50, 2" (TON)	35501316 HMA BASE COURSE, 8" (SQ YD)	35501308 HMA BASE COURSE, 6" (SQ YD)	42300400 PCC DRIVEWAY PAVEMENT, 8" (SQ YD)	35102000 AGGREGATE BASE COURSE, TYPE B, 8" (SQ YD)	
ROUTE 14																
504+00.00	LT				225											
510+34.00	LT		22	45	532	373	383		127	20						
522+49.40	RT	21									7.3			65		
525+80.00	LT	40														
526+45.10	LT				65					10.6			95			
527+25.00	LT	45														
532+21.62	LT				156	66	60	46	43		8.0	70				
532+51.28	LT				156	66	60	46	43		8.0	73				
532+52.70	RT	38									7.6		68			
561+35.90	RT				176						15.4		137			
562+00.00	RT				47											
564+62.40	LT				95	92		33			7.8	44				
566+91.50	LT				124	122		48			5.0	63				
573+60.90	LT				31						7.1	62				
577+85.00	RT				170	36		35			16.8	56				
579+79.28	RT				35											
580+02.70	LT				101	86			37		4.4		39			
580+54.10	RT				285		108		37		6.3	56				
582+84.30	RT				171		211	64			9.6	101				
583+73.40	LT				89						6.6		71			
584+88.50	LT				67						5.8		51			
585+61.70	LT				126	50	61	50	54					117		
585+71.77	RT								69					75		
586+02.70	RT				110	17	122									
587+49.40	LT				142		199									
591+24.10	LT				176	73	46	55	43					120		
592+21.50	RT				30						6.5					58
592+92.30	RT				37						6.9					55
595+20.80	LT				230		57		112		9.5	66				
596+78.90	RT				22						4.8					43
597+55.50	LT				128		58		42		8.8	78				
602+09.90	RT				14						4.7					42
603+25.80	LT				107		71	58			8.7	78				
603+94.50	RT				26						5.7					51
606+48.72	RT				214	120			104					205		
611+05.20	RT				109		52		68					102		
612+36.30	RT				62	25		38			6.0	53				
613+17.30	LT				65	37		44						59		
614+75.00	RT				51	24		41						59		
614+92.20	LT				40			33			6.8	61				
616+24.80	RT				29			36			5.4	48				
616+45.50	LT				18						4.2		37			
RIDGEFIELD ROAD SOUTH																
903+20.60	LT				146	115			102		15.5	139				
LENNY DR																
Cul-se-sac					49					4.9		44				
IL 176																
593+65.00	LT				183	75		44	34		11.5	103				
594+14.40	LT				176	64		44	30		11.5	103				
597+37.50	LT				75		26	19	26					73		
597+65.70	LT				75		26	19	26					73		
601+97.57	RT				90		65	29	48					85		
602+43.00	LT				103		56	35	44					77		
603+64.20	RT				89		61		49					94		
604+23.00	LT				78		62		44					57		
604+35.30	RT				95		61		51		8.8	78				
605+15.80	LT				105		68		42					79		
605+66.00	LT				78		98									
606+27.20	LT				71	48		29	21		6.6	59				
606+91.80	LT				52	50		54			5.9	52				
607+69.30	LT				27						3.6		32			
LUCAS RD																
6+81.55	LT	5									1.9					17
8+09.30	LT				66						5.1		45			
		149	22	45	532	5,658	1,549	1,628	1,129	1,067	20	281	1,443	683	1,275	266

ITEM 21101685 TOPSOIL FURNISH AND PLACE, 24"	
LOCATION STATION TO STATION	AREA (SQ YD)
US RTE 14	
493+00 TO 505+00	234
505+00 TO 520+00	1,311
520+00 TO 535+00	1,256
535+00 TO 550+00	2,341
550+00 TO 565+00	2,527
565+00 TO 578+00	411
578+00 TO 593+00	742
593+00 TO 599+00	0
599+00 TO 608+00	0
608+00 TP 619+26.50	0
LUCAS RD	
3+27.60 TO 15+76.00	211
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	0
904+25.00 TO 907+07.35	0
LENNY DR	
00+37.11 TO 04+39.21	0
IL 176	
590+23.80 TO 599+44.15	0
600+57.53 TO 608+50.50	0
TOTAL	9,033

ITEM 40603080 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	
LOCATION STATION TO STATION	TON
US RTE 14	
493+00 TO 505+00	165 MULTI-USE PATH
505+00 TO 520+00	104 MULTI-USE PATH
520+00 TO 535+00	0
535+00 TO 550+00	0
550+00 TO 565+00	0
565+00 TO 578+00	0
578+00 TO 593+00	0
593+00 TO 599+00	0
599+00 TO 608+00	0
608+00 TP 619+26.50	0
LUCAS RD	
3+27.60 TO 15+76.00	0
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	0
904+25.00 TO 907+07.35	0
LENNY DR	
00+37.11 TO 04+39.21	0
IL 176	
590+23.80 TO 599+44.15	0
600+57.53 TO 608+50.50	0
TOTAL	269