

PAVEMENT PATCHING SCHEDULE

ALIGNMENT	STATION	AREA (SY)	EX. PVMT DEPTH (IN)	TYPE	PAY ITEM NO.	PAY ITEM ABBR.
LUCAS	9+12.91	15.2	9	T3	44200112	PAVT PATCH T3 9
LUCAS	9+36.20	18.5	9	T3	44200112	PAVT PATCH T3 9
LUCAS	9+53.36	21.0	9	T3	44200112	PAVT PATCH T3 9
US 14	510+33.06	40.5	15	T4	44200186	PAVT PATCH T4 15
US 14	535+40	28.4	15	T4	44200186	PAVT PATCH T4 15
US 14	536+00	22.2	15	T3	44200184	PAVT PATCH T3 15
US 14	537+29	22.0	15	T3	44200184	PAVT PATCH T3 15
US 14	538+03	26.3	15	T4	44200186	PAVT PATCH T4 15
US 14	538+10	22.2	15	T3	44200184	PAVT PATCH T3 15
US 14	538+50	22.0	15	T3	44200184	PAVT PATCH T3 15
US 14	538+91	22.0	15	T3	44200184	PAVT PATCH T3 15
US 14	540+20	22.1	15	T3	44200184	PAVT PATCH T3 15
US 14	541+45	21.9	15	T3	44200184	PAVT PATCH T3 15
US 14	544+70	22.1	15	T3	44200184	PAVT PATCH T3 15
US 14	546+15	21.9	15	T3	44200184	PAVT PATCH T3 15
US 14	547+60	22.0	15	T3	44200184	PAVT PATCH T3 15
US 14	549+05	22.0	15	T3	44200184	PAVT PATCH T3 15
US 14	549+91	26.1	15	T4	44200186	PAVT PATCH T4 15
US 14	550+20	22.1	15	T3	44200184	PAVT PATCH T3 15
US 14	550+74	21.3	15	T3	44200184	PAVT PATCH T3 15
US 14	551+09.46	21.5	15	T3	44200184	PAVT PATCH T3 15
US 14	551+25	19.7	15	T3	44200184	PAVT PATCH T3 15
US 14	552+35	20.7	15	T3	44200184	PAVT PATCH T3 15
US 14	553+53	22.0	15	T3	44200184	PAVT PATCH T3 15
US 14	554+32	21.8	15	T3	44200184	PAVT PATCH T3 15
US 14	556+10	21.9	15	T3	44200184	PAVT PATCH T3 15
US 14	558+40	21.6	15	T3	44200184	PAVT PATCH T3 15
US 14	560+68	21.7	17	T3	44200204	PAVT PATCH T3 17
US 14	564+30	26.2	17	T4	44200206	PAVT PATCH T4 17
US 14	572+00	36.6	17	T4	44200206	PAVT PATCH T4 17
US 14	572+00	36.2	17	T4	44200206	PAVT PATCH T4 17
LENNY DR	2+02	26.5	6	T4	44200071	PAVT PATCH T4 6
US 14	578+50	19.7	17	T3	44200204	PAVT PATCH T3 17
US 14	580+30	22.7	17	T3	44200204	PAVT PATCH T3 17
US 14	582+20	19.7	16	T3	44200196	PAVT PATCH T3 16
US 14	582+80	19.7	16	T3	44200196	PAVT PATCH T3 16
US 14	583+45	21.9	16	T3	44200196	PAVT PATCH T3 16
US 14	583+90	24.4	16	T3	44200196	PAVT PATCH T3 16
US 14	585+23	28.1	16	T4	44200198	PAVT PATCH T4 16
US 14	587+40	29.4	16	T4	44200198	PAVT PATCH T4 16
US 14	590+93	33.3	16	T4	44200198	PAVT PATCH T4 16
US 14	593+70	28.1	16	T4	44200198	PAVT PATCH T4 16
US 14	594+60	28.1	16	T4	44200198	PAVT PATCH T4 16
US 14	597+70	28.1	16	T4	44200198	PAVT PATCH T4 16
US 14	600+65	29.2	16	T4	44200198	PAVT PATCH T4 16
US 14	603+29	28.1	16	T4	44200198	PAVT PATCH T4 16
US 14	605+57	28.1	16	T4	44200198	PAVT PATCH T4 16
US 14	606+48.72	30.2	16	T4	44200198	PAVT PATCH T4 16
US 14	607+85	28.1	16	T4	44200198	PAVT PATCH T4 16
US 14	609+15.18	22.6	16	T3	44200196	PAVT PATCH T3 16
US 14	610+61	28.1	16	T4	44200198	PAVT PATCH T4 16
US 14	611+05.2	19.6	16	T3	44200196	PAVT PATCH T3 16
US 14	612+00	31.0	16	T4	44200198	PAVT PATCH T4 16
US 14	612+36.3	26.0	16	T4	44200198	PAVT PATCH T4 16
US 14	614+60	39.3	16	T4	44200198	PAVT PATCH T4 16
US 14	614+75	26.9	16	T4	44200198	PAVT PATCH T4 16
US 14	616+05	39.1	16	T4	44200198	PAVT PATCH T4 16
US 14	616+24.8	25.0	16	T4	44200198	PAVT PATCH T4 16
US 14	617+60	38.6	16	T4	44200198	PAVT PATCH T4 16
IL 176	595+00	18.6	13	T3	44200160	PAVT PATCH T3 13
IL 176	596+70	21.2	13	T3	44200160	PAVT PATCH T3 13
IL 176	601+20	6.3	13	T2	44200156	PAVT PATCH T2 13
IL 176	601+26	18.8	13	T3	44200160	PAVT PATCH T3 13
IL 176	602+43	28.8	13	T4	44200162	PAVT PATCH T4 13
IL 176	602+82	12.6	13	T2	44200156	PAVT PATCH T2 13

ITEM AGGREGATE SHOULDERS, TYPE B 9"	
LOCATION STATION TO STATION	SQ YD
US RTE 14	
493+00 TO 505+00	0
505+00 TO 520+00	0
520+00 TO 535+00	0
535+00 TO 550+00	0
550+00 TO 565+00	0
565+00 TO 578+00	0
578+00 TO 593+00	0
593+00 TO 599+00	0
599+00 TO 608+00	0
608+00 TP 619+26.50	0
LUCAS RD	
3+27.60 TO 15+76.00	761
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	334
904+25.00 TO 907+07.35	456
LENNY DR	
00+37.11 TO 04+39.21	0
IL 176	
590+23.80 TO 599+44.15	0
600+57.53 TO 608+50.50	0
TOTAL	1,551

ITEM AGGREGATE SHOULDERS, TYPE B 9 3/4"	
LOCATION STATION TO STATION	SQ YD
US RTE 14	
493+00 TO 505+00	0
505+00 TO 520+00	0
520+00 TO 535+00	0
535+00 TO 550+00	0
550+00 TO 565+00	0
565+00 TO 578+00	0
578+00 TO 593+00	0
593+00 TO 599+00	0
599+00 TO 608+00	0
608+00 TP 619+26.50	0
LUCAS RD	
3+27.60 TO 15+76.00	0
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	0
904+25.00 TO 907+07.35	0
LENNY DR	
00+37.11 TO 04+39.21	0
IL 176	
590+23.80 TO 599+44.15	35
600+57.53 TO 608+50.50	127
TOTAL	162

ITEM 48203033 HOT-MIX ASPHALT SHOULDERS, 9"	
LOCATION STATION TO STATION	SQ YD
US RTE 14	
493+00 TO 505+00	0
505+00 TO 520+00	0
520+00 TO 535+00	0
535+00 TO 550+00	0
550+00 TO 565+00	0
565+00 TO 578+00	0
578+00 TO 593+00	0
593+00 TO 599+00	0
599+00 TO 608+00	0
608+00 TP 619+26.50	0
LUCAS RD	
3+27.60 TO 15+76.00	0
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	133
904+25.00 TO 907+07.35	90
LENNY DR	
00+37.11 TO 04+39.21	0
IL 176	
590+23.80 TO 599+44.15	0
600+57.53 TO 608+50.50	0
TOTAL	223

ITEM 60603800 COMBINATION CURB AND GUTTER, TYPE B-6.12	
LOCATION STATION TO STATION	FOOT
US RTE 14	
493+00 TO 505+00	0
505+00 TO 520+00	0
520+00 TO 535+00	86
535+00 TO 550+00	0
550+00 TO 565+00	0
565+00 TO 578+00	0
578+00 TO 593+00	303
593+00 TO 599+00	162
599+00 TO 608+00	0
608+00 TP 619+26.50	36
LUCAS RD	
3+27.60 TO 15+76.00	870
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	0
904+25.00 TO 907+07.35	0
LENNY DR	
00+37.11 TO 04+39.21	645
IL 176	
590+23.80 TO 599+44.15	70
600+57.53 TO 608+50.50	431
TOTAL	2,603

ITEM 60605000 COMBINATION CURB AND GUTTER, TYPE B-6.24	
LOCATION STATION TO STATION	FOOT
US RTE 14	
493+00 TO 505+00	3,801
505+00 TO 520+00	5,534
520+00 TO 535+00	5,000
535+00 TO 550+00	5,996
550+00 TO 565+00	6,000
565+00 TO 578+00	4,289
578+00 TO 593+00	4,872
593+00 TO 599+00	2,176
599+00 TO 608+00	2,079
608+00 TP 619+26.50	2,469
LUCAS RD	
3+27.60 TO 15+76.00	384
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	0
904+25.00 TO 907+07.35	0
LENNY DR	
00+37.11 TO 04+39.21	122
IL 176	
590+23.80 TO 599+44.15	1,662
600+57.53 TO 608+50.50	407
TOTAL	44,791

ITEM 60618300 CONCRETE MEDIAN SURFACE, 4 INCH	
LOCATION STATION TO STATION	SQ FT
US RTE 14	
493+00 TO 505+00	5,124
505+00 TO 520+00	5,825
520+00 TO 535+00	2,296
535+00 TO 550+00	2,153
550+00 TO 565+00	1,706
565+00 TO 578+00	2,822
578+00 TO 593+00	4,591
593+00 TO 599+00	5,210
599+00 TO 608+00	0
608+00 TP 619+26.50	0
LUCAS RD	
3+27.60 TO 15+76.00	0
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	0
904+25.00 TO 907+07.35	0
LENNY DR	
00+37.11 TO 04+39.21	0
IL 176	
590+23.80 TO 599+44.15	0
600+57.53 TO 608+50.50	0
TOTAL	29,727

FILE NAME = S:\1606\CADD Sheets\0162517-sht-schedule.dgn	USER NAME = .USERNAME.	DESIGNED - JPW	REVISED -
		DRAWN - JPW	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED - MGZ	REVISED -
	PLOT DATE = 11/5/2013	DATE - 10/15/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 24 OF 431 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-3	MCHENRY	431	24
CONTRACT NO. 62517				
ILLINOIS FED. AID PROJECT				