

ITEM 48300415 PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	
LOCATION STATION TO STATION	SQ YD
US RTE 14	
493+00 TO 505+00	0
505+00 TO 520+00	0
520+00 TO 535+00	0
535+00 TO 550+00	0
550+00 TO 565+00	0
565+00 TO 578+00	0
578+00 TO 593+00	0
593+00 TO 599+00	0
599+00 TO 608+00	0
608+00 TP 619+26.50	0
LUCAS RD	
3+27.60 TO 15+76.00	0
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	83
904+25.00 TO 907+07.35	28
LENNY DR	
00+37.11 TO 04+39.21	0
IL 176	
590+23.80 TO 599+44.15	333
600+57.53 TO 608+50.50	577
TOTAL	1,021

ITEM 30300112 AGGREGATE SUBGRADE IMPROVEMENT 12"	
LOCATION STATION TO STATION	AREA (SQ YD)
US RTE 14	
493+00 TO 505+00	12,385
505+00 TO 520+00	12,580
520+00 TO 535+00	12,142
535+00 TO 550+00	10,812
550+00 TO 565+00	10,656
565+00 TO 578+00	12,182
578+00 TO 593+00	14,460
593+00 TO 599+00	5,582
599+00 TO 608+00	3,841
608+00 TO 619+26.50	3,034
COLLEGE ENTRANCE #3	
11+09.48 TO 15+76.00	2034
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	2,531
904+25.00 TO 907+07.35	639
LENNY DR	
00+37.11 TO 04+39.21	1,400
IL 176	
590+23.80 TO 599+44.15	5,646
600+57.53 TO 608+50.50	5,489
LUCAS RD	
3+27.60 TO 8+38.10	1268
ROCKLAND RD	
10+00.00 TO 11+06.50	287
HICKORY DR	
10+35.59 TO 10+89.00	206
TOTAL	117,174

ITEM 70300100 SHORT TERM PAVEMENT MARKING	
LOCATION STATION TO STATION	FOOT
US RTE 14	
493+00 TO 505+00	110.00
505+00 TO 520+00	137.00
520+00 TO 535+00	137.00
535+00 TO 550+00	137.00
550+00 TO 565+00	137.00
565+00 TO 578+00	137.00
578+00 TO 593+00	137.00
593+00 TO 599+00	53.00
599+00 TO 608+00	504.00
608+00 TP 619+26.50	610.00
COLLEGE ENTRANCE #3	
11+09.48 TO 15+76.00	0
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	0
904+25.00 TO 907+07.35	0
LENNY DR	
00+37.11 TO 04+39.21	0
IL 176	
590+23.80 TO 599+44.15	111
600+57.53 TO 608+50.50	100
TOTAL	2,310

ITEM 78100100 RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION STATION TO STATION	EACH
US RTE 14	
493+00 TO 505+00	69
505+00 TO 520+00	85
520+00 TO 535+00	86
535+00 TO 550+00	75
550+00 TO 565+00	75
565+00 TO 578+00	83
578+00 TO 593+00	82
593+00 TO 599+00	38
599+00 TO 608+00	84
608+00 TP 619+26.50	121
LUCAS RD	
3+27.60 TO 15+76.00	57
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	20
904+25.00 TO 907+07.35	22
LENNY DR	
00+37.11 TO 04+39.21	13
IL 176	
590+23.80 TO 599+44.15	30
600+57.53 TO 608+50.50	45
TOTAL	985

ITEM 78300100 PAVEMENT MARKING REMOVAL	
LOCATION STATION TO STATION	SQ FT
US RTE 14	
493+00 TO 505+00	967
505+00 TO 520+00	1,039
520+00 TO 535+00	880
535+00 TO 550+00	1,500
550+00 TO 565+00	1,500
565+00 TO 578+00	488
578+00 TO 593+00	1,306
593+00 TO 599+00	650
599+00 TO 608+00	1,080
608+00 TP 619+26.50	833
LUCAS RD	
3+27.60 TO 15+76.00	0
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	0
904+25.00 TO 907+07.35	0
LENNY DR	
00+37.11 TO 04+39.21	0
IL 176	
590+23.80 TO 599+44.15	627
600+57.53 TO 608+50.50	541
TOTAL	11,411

ITEM 20062456 TEMPORARY PAVEMENT	
LOCATION STATION TO STATION	SQ YD
US RTE 14	
493+00 TO 505+00	4,258
505+00 TO 520+00	4,157
520+00 TO 535+00	357
535+00 TO 550+00	777
550+00 TO 565+00	610
565+00 TO 578+00	2,059
578+00 TO 593+00	1,495
593+00 TO 599+00	1,587
599+00 TO 608+00	815
608+00 TP 619+26.50	243
LUCAS RD	
3+27.60 TO 15+76.00	842
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	423
904+25.00 TO 907+07.35	595
LENNY DR	
00+37.11 TO 04+39.21	250
IL 176	
590+23.80 TO 599+44.15	3,054
600+57.53 TO 608+50.50	2,290
TOTAL	23,812

ITEM 70301000 WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION STATION TO STATION	SQ FT
US RTE 14	
493+00 TO 505+00	5,714
505+00 TO 520+00	3,712
520+00 TO 535+00	4,149
535+00 TO 550+00	3,046
550+00 TO 565+00	3,049
565+00 TO 578+00	4,180
578+00 TO 593+00	4,193
593+00 TO 599+00	1,300
599+00 TO 608+00	2,448
608+00 TP 619+26.50	890
LUCAS RD	
3+27.60 TO 15+76.00	1,304
RIDGEFIELD RD SOUTH	
900+45.32 TO 904+25.00	1,489
904+25.00 TO 907+07.35	1,563
LENNY DR	
00+37.11 TO 04+39.21	630
IL 176	
590+23.80 TO 599+44.15	1,780
600+57.53 TO 608+50.50	1,641
TOTAL	41,088

FILE NAME = S:\1606\CADD Sheets\0162517-sht-schedule.dgn	USER NAME = .USERNAME.	DESIGNED - JPW	REVISED -
		DRAWN - JPW	REVISED -
		CHECKED - MGZ	REVISED -
		DATE - 10/15/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: NONE      SHEET NO. 26 OF 431 SHEETS      STA.      TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-3	MCHENRY	431	26
CONTRACT NO. 62517				
ILLINOIS FED. AID PROJECT				