

TRANSVERSE UNDERDRAIN SCHEDULE

STATION	U/S INV	UNDERDRAIN	UNDERDRAIN SPECIAL	SLOPE	CONNECTING	D/S INV.
	ELEVE.	LENGTH (FT)	LENGTH (FT)	(%)	STR NO.	ELEVE.
516+72.50	916.30	34.1	5	0.30	319	916.18
516+86.00	916.97	35.1	5	2.00	419	916.17
519+55.00	916.02	73.2	5	2.46	425	914.09
523+20.00	914.86	73.1	5	3.21	431	912.35
525+32.00	913.61	73.1	5	3.21	438	911.10
527+55.00	915.43	73.1	5	3.21	444	912.92
533+55.00	917.33	73.1	5	3.10	454	914.91
535+95.00	910.91	73.1	5	0.30	460	910.67
538+15.00	910.01	73.1	5	0.30	469	909.77
540+25.00	910.87	73.1	5	0.30	501	910.63
544+65.00	911.25	73.1	5	0.30	501	911.01
547+55.00	909.29	73.1	5	0.30	507	909.05
550+79.00	907.41	73.1	5	0.30	525	907.17
553+57.00	909.88	72.1	5	2.00	533	908.34
556+14.00	912.16	72.1	5	3.02	539	909.83
558+44.00	913.74	72.1	5	3.02	542	911.41
560+72.00	915.20	72.1	5	2.88	545	912.98
566+20.00	915.25	76.2	5	2.41	605	913.29
568+07.00	915.15	85.6	5	3.87	608	911.64
570+45.09	913.56	53.5	5	3.87	613	911.30
570+54.59	913.56	30.3	5	3.87	612	912.20
572+65.00	914.65	77.5	5	3.87	626	911.46
574+55.00	917.66	73.1	5	3.87	630	914.64
580+25.00	914.22	76.2	5	0.30	709	913.97
583+40.00	910.29	89.1	5	0.30	723	910.00
586+75.00	905.59	80.6	5	0.30	737	905.33
Total		1803.9	130			

LONGITUDINAL UNDERDRAIN SCHEDULE

STA	TO	U/S INV.	U/S INV.	UNDERDRAIN	UNDERDRAIN SPECIAL	SLOPE	D/S INV.
			ELEVE.	LENGTH (FT)	LENGTH (FT)	(%)	ELEVE.
601+00		901.08	37			0.30	
601+37							
601+37			188.9	1		0.50	900.97
601+37						0.30	900.96
603+25		901.53					900.97
607+00		901.87	81.54				
607+84				5		0.30	
610+00		903.13	57.9				901.61
610+60				5		0.30	
610+66		902.99	44.54				902.94
010+53							
612+01			47.34	5		0.33	903.18
612+50		903.35					
601+00		901.19	37			0.85	
601+37				1		0.50	900.88
601+37			186			0.30	900.87
603+24		901.43					900.88
607+00		901.87	80.8				
607+83				5		0.30	
610+00		903.13	56.14				901.61
610+59				5		0.30	
612+02			45.24				902.95
612+50		903.35		5		0.33	903.19
Total			862.4	37			