


NOTE:  
THE TEMPORARY TRAFFIC SIGNAL AT COLLEGE ENTRANCE #1  
MUST REMAIN OPERATIONAL UNTIL THIS SIGNAL IS PLACED  
INTO OPERATION.

NOTE:  
THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT  
SHALL BE "ECONOLITE" TO MATCH EXISTING ADJACENT SYSTEM.

RESTORATION OF WORK AREA: RESTORATION OF THE TRAFFIC  
WORK AREA SHALL BE INCLUDED IN THE COST OF THE RELATED  
PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH,  
AND BACKFILL ETC. AND NO EXTRA COMPENSATION SHALL BE  
ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS,  
MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN  
KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH  
AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL  
BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252  
AND 250 RESPECTIVELY.

**EJM ENGINEERING, INC.**  
411 South Wells Street Suite 1000  
Chicago, Illinois 60607



FILE NAME =  
...\\0162517-SHT-TS01.dgn

USER NAME = rswanson  
PLOT SCALE = 20:1  
PLOT DATE = 5/16/2014

DESIGNED - GR  
DRAWN - GR  
CHECKED - RS  
DATE - 10/15/2013

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**TRAFFIC SIGNAL INSTALLATION PLAN  
US RTE. 14 AND COLLEGE ENTRANCE NO. 3**  
SCALE: 20:1 SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-3	MCHENRY	431	290
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 62517	