

MAINLINE								
STATIONS	HMA SURF REM	MIX FOR CRKS JTS FLANGE	LEV BIND (HM) N70	BIT MAT PRIME COAT	LEV BIND (MM) IL 9.5FG N70	HMA SURF CSE MIX "D" N70	AGG WEDGE SHLDS TY B	TEMP RAMP
	2 1/4" SQ YD	TON	TON	POUND	TON	TON	TON	SQ YD
11+74 - 20+29	3970	1.19	1.84	2615.9	166.7	333.5	24.8	20
20+29 - 29+39	3547	1.06	1.31	2187.7	149.0	297.9	16.2	
29+39 - 32+50	898	0.27	0.45	606.2	37.7	75.4	13.3	
32+50 - 35+48(WOODEN BRIDGE)	1146	0.34	0.43	709.4	48.1	96.3	11.4	
35+48 - 39+24	1087	0.33	0.54	733.7	45.7	91.3	16.1	
39+24 - 42+50(CROOKED CREEK)	1261	0.38	0.47	779.4	53.0	105.9	12.5	
42+50 - 59+00	4767	1.43	2.38	3217.7	200.2	400.4	70.5	
59+00 - 60+91.56	639	0.19	0.32	431.3	26.8	53.7	8.2	
60+91.56 - 72+57.91	3888	1.17	1.94	2624.4	163.3	326.6	45.0	
72+57.91 - 78+56	2592	0.78	1.30	1749.6	108.9	217.7	25.5	30
TOTALS	23795	7	11	15655	999	1999	243	50

CURB & SIDEWALK SCHEDULE						
DESCRIPTION	COMB. CURB & GUTTER REM	CC & G B6-12	SIDEWALK REM	PCC SIDEWALK 4"	DETECTABLE WARNING	SODDING SALT TOLERANT
	FOOT	FOOT	SQ FT	SQ FT	SQ FT	SQ YD
ACROSS IL 126						
NORTH	0	0	75	75	10	7.00
SOUTH	15	15	64	64	10	7.00
COLONIAL PARKWAY						
NORTHWEST CORNER	10	10	52	52	8	4.00
SOUTHEAST CORNER	10	10	34	34	8	6.00
TOTAL	35	35	225	225	36	24

SIDEROADS AND ENTRANCES					
STATION	DESCRIPTION	HMA SURF REM	BIT MATLS PR CT	INC HMA SURF	TEMP RAMP
		2 1/4" SQ YD	POUND	TON	SQ YD
12+08 LT	CE	57	26	7	
13+16 RT	CE	95	43	12	
15+35 LT	CE	205	92	26	
15+40 RT	CE	64	29	8	
21+18 RT	COLONIAL PARKWAY	86	39	11	25
21+66 LT	MILL STREET	176	79	22	16.7
23+63 RT	DEER STREET	314	141	40	
26+62 RT	CE	126	57	16	
29+78 LT	PE	18	8	2	
29+92 RT	PE	18	8	2	
35+09 RT	WOODEN BRIDGE RD	63	28	8	21.6
42+07 RT	CROOKED CREEK RD	67	30	8	21.6
43+71 LT	PE	18	8	2	50
65+50 RT	IDENTA RD	238	107	30	49.2
TOTALS		1545	695	195	184

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p1dot\duncanbd\dms84419\ED005104-sht-schedule.dgn	DRAWN -	REVISED -	379					118R5-3	KENDALL	19	8	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 66473									
PLOT DATE = 6/4/2014	DATE -	REVISED -	SCALE:		SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			